




# Hydrogeology and Water Supply Wells

## *Catoctin Mountain Park*

Natural Resource Report NPS/NRPC/WRD/NRTR—2007/374



**ON THE COVER**

Entrance to Catoctin Mountain Park

Photograph by: Frank Noe, Baltimore, MD

---

# **Hydrogeology and Water Supply Wells**

## ***Catoctin Mountain Park***

Natural Resource Report NPS/NRPC/WRD/NRTR—2007/374

Larry Martin  
National Park Service  
Water Resources Division  
1201 Oak Ridge Drive, Suite 250  
Ft. Collins, CO 80525

June 2007

U.S. Department of the Interior  
National Park Service  
Natural Resources Program Center  
Ft. Collins, Colorado

The Natural Resource Publication series addresses natural resource topics that are of interest and applicability to a broad readership in the National Park Service and to others in the management of natural resources, including the scientific community, the public, and the NPS conservation and environmental constituencies. Manuscripts are peer-reviewed to ensure that the information is scientifically credible, technically accurate, appropriately written for the intended audience, and is designed and published in a professional manner.

The Natural Resources Technical Reports series is used to disseminate the peer-reviewed results of scientific studies in the physical, biological, and social sciences for both the advancement of science and the achievement of the National Park Service's mission. The reports provide contributors with a forum for displaying comprehensive data that are often deleted from journals because of page limitations. Current examples of such reports include the results of research that addresses natural resource management issues; natural resource inventory and monitoring activities; resource assessment reports; scientific literature reviews; and peer reviewed proceedings of technical workshops, conferences, or symposia.

Views and conclusions in this report are those of the authors and do not necessarily reflect policies of the National Park Service. Mention of trade names or commercial products does not constitute endorsement or recommendation for use by the National Park Service.

Printed copies of reports in these series may be produced in a limited quantity and they are only available as long as the supply lasts. This report is also available from the Water Resources Division Technical Reports website on the internet or by sending a request to the address on the back cover. (<http://www.nature.nps.gov/water/technicalReports/ReportsIndex.cfm>)

Please cite this publication as:

Martin, Larry, 2007, *Hydrogeology and Water Supply Wells, Catoctin Mountain Park* NPS/NRPC/WRD/NRTR—2007/374, National Park Service, Ft. Collins, CO.

NPS D-32, June 2007

# Contents

	Page
Summary .....	v
Introduction.....	1
Previous Investigations .....	1
Geology and Hydrogeology .....	2
Well Inventory .....	5
Water Systems/Active Wells .....	5
Headquarters .....	7
Blue Blazes .....	7
Round Meadow .....	9
Jim Brown Well No. 2 .....	9
Jim Brown Well No. 4 .....	10
Ike Smith Water System .....	11
Poplar Grove Wells.....	11
Ike Smith Well .....	11
Quarters No. 5 .....	12
Quarters No. 6.....	13
Inactive Wells .....	13
Misty Mount/Blue Blazes Area .....	13
Ike Smith Springs Area.....	15
Greentop.....	15
Jim Brown.....	16
Water Use and Potential for Streamflow Depletion .....	18
Recommended Locations for Well Construction.....	19
Typical Well Construction.....	20
Recommendations.....	21
Glossary .....	23
Literature Cited .....	24
Appendix—Well Completion Reports.....	25

## Figures

	Page
Figure 1. Physiographic setting of Catoctin Mountain Park .....	2
Figure 2. Geologic map and cross section of Catoctin Mountain Park .....	4
Figure 3. Location of the Headquarters and Blue Blazes Wells .....	8
Figure 4. Water level drawdown and recovery during testing of Blue Blazes Well No. 2.....	9
Figure 5. Locations of wells for the Round Meadow and Ike Smith water systems .....	10
Figure 6. Water level drawdown and recovery during testing of the Ike Smith Well .....	12
Figure 7. Inactive wells in the Misty Mount/Blue Blazes area.....	14
Figure 8. Inactive wells in the Ike Smith, Greentop, Jim Brown areas .....	17
Figure 9. Hydrogeologic model for siting well locations .....	19
Figure 10. Typical well construction at Catoctin Mountain Park.....	21

## Tables

	Page
Table 1. Wells in Catoctin Mountain Park.....	6

## List of Acronyms

gpm	gallons per minute	
gpd	gallons per day	
cfs	cubic feet per second	1 cfs = 450 gpm

## Summary

Groundwater pumped from wells in Catoctin Mountain Park is obtained from fractures in the underlying metamorphic rocks. There appears to be no consistent relationship between the hydrogeologic setting of well locations and well yield. Wells within close proximity and constructed in similar hydrogeologic settings may produce large volumes of water, or nearly nothing. Well yield is entirely dependent on the amount of fractured rock encountered at depth and the water-bearing characteristics of those fractures.

The potential for constructing wells with large yields can be increased by locating them on the east side of stream valleys. Infiltration of water in stream valleys will eventually reach the underlying southeasterly dipping bedrock and follow bedding planes and fractures downdip, toward the southeast. Thus, a well located downdip of a stream (recharge source) will have a better chance of producing water than wells in other locations.

There is sufficient pumping capacity from existing wells in the park to meet current demand. No additional facilities are planned. If additional supplies are needed in the future, some of the existing low-volume wells could be developed as supplemental water sources.





## **Introduction**

Catoctin Mountain Park covers nearly 6000 acres of mountainous terrain in the Blue Ridge Province of western Maryland. The park contains several camp/cabin areas dating back to the era of the Great Depression. Over the years, approximately 20 wells have been drilled in the park to provide water for NPS facilities. Only about half of those wells were deemed successful; producing enough water to be developed and equipped with pumps.

This report summarizes the hydrogeology and the history of well drilling in the park. Although there appears to be no definite pattern or geologic conditions that will insure successful well drilling, the chances for success can be improved by locating future wells on the east side of perennial streams to take advantage of the streams as a potential source of groundwater recharge.

## **Previous Investigations**

The geology of the park and surrounding area has been mapped by Whitaker (1955), Fauth (1977), and Southworth and Denenny (2006).

Nutter (1971) supervised construction and testing of a water supply well at the Camp Peniel environmental education center. The facility is now the headquarters and administrative offices for the park.

Huth Engineers (1981) evaluated wastewater disposal systems, water supply systems, and fire protection systems for the Camp Greentop and Camp Round Meadow areas.

Trombley and Zynjuk (1985) reported on the hydrogeology and water quality of the park. Their work included sampling and analyses of water quality for wells, springs, and streams throughout the park. They also supervised construction and testing of a new well at Quarters #5 and investigated the potential for infiltration from sewage treatment facilities at Camp Round Meadow to affect groundwater quality at nearby wells.

Dine, Tompkins, and Duigon (1985) compiled basic data for water wells in Frederick County. Duigon and Dine (1987) provided an assessment of water resources of Frederick County to provide the basic hydrologic background for planning, development, and other activities.

## Geology and Hydrogeology

Catoctin Mountain Park is situated on the east limb of the Blue Ridge-South Mountain anticlinorium, immediately west of the transition from the Piedmont to the Blue Ridge physiographic provinces (Figure 1). Geologic formations underlying the park dip toward the southeast (Southworth and Denenny, 2006).




Figure 1. Physiographic setting of Catoctin Mountain Park.

The park is underlain by PreCambrian metamorphic rocks. The western part of the park is underlain by Catoctin Formation. The two main types of rocks comprising the Catoctin Formation are a greenish-gray metabasalt and a bluish-grayish metarhyolite. The eastern part of the park is underlain by the Loudoun Formation, which is comprised of phyllite and conglomerate units. Overlying the Loudoun, and outcropping in the very eastern part of the park, is the Weverton Formation. The Weverton is comprised of a sequence of interbedded quartzite, phyllite, and conglomerate. A geologic map of the park and a geological cross section are provided in Figure 2.

The metabasalt and metarhyolite rocks comprising the Catoctin Formation were originally deposited as molten rock from volcanic eruptions. The volcanic rocks were later covered by quartz sand deposited as river sediments. These geologic units were subsequently buried and

subjected to heat and pressure to metamorphose into their current state. The units were then uplifted by mountain-building processes and uncovered by erosion of the overlying rocks.

Landforms and topography in Catoctin Mountain Park are largely a function of the type of bedrock. The rock near the contacts between geologic units tends to be more fractured, and thus more easily eroded, than rock from the interior parts of the formations. Linear valleys that parallel the northeast-trending bedding and foliation planes of the bedrock have formed along the contacts between the Catoctin and Loudoun Formations and between the metabasalt and metarhyolite comprising the Catoctin Formation (Southworth and Denenny, 2006).

Rock units in the park are highly fractured and folded. The major axes of folding and cleavage planes strike northeast-southwest. Cleavage along bedding planes and fractures dip toward the southeast at approximately 45 degrees (Trombley and Zynjuk, 1985).

Groundwater in the park occurs in the regolith zone overlying unweathered bedrock and within fracture zones in the bedrock. The regolith is comprised of all of the soil and rock material overlying the unaltered bedrock and includes both material that has been transported and material that has weathered in place. The regolith is thinner at the top of Catoctin Mountain and along ridges and thicker in the valleys. The regolith has moderate porosity and permeability. It is the principal aquifer in the park. Groundwater also occurs in the openings along bedding planes, cleavage planes, joints, and faults within the bedrock. The number, size, and interconnectivity of these openings determine the water-producing potential of the bedrock. In general, bedrock openings decrease with depth as the weight of the overlying rock tends to squeeze the openings closed. Areas underlying valleys tend to be better locations for wells because there is a constant source of recharge from infiltration of water from streams.




Figure 2. Geologic map and cross section of Catoclin Mountain Park (from Southworth and Denenny, 2006).

Trombley and Zynjuk (1985) estimate that the regolith extends to a depth of about 200 feet at Camp Round Meadow. The regolith is less thick beneath the ridges and mountains. The success of a well constructed at Catoction depends on the thickness of the regolith, the thickness and degree of fracturing in the bedrock, and the degree of interconnectivity with surrounding fractured rock. As a general guideline, test holes for water supply wells probably do not need to exceed 300 feet deep.

## **Well Inventory**

Table 1 is a listing of all wells in Catoctin Mountain Park. It does not include wells and test holes at The Presidential Retreat or the Naval Support Facility, Thurmont, at Round Meadow. Well completion reports (as available) are attached as an appendix to this report. Well completion reports could not be found for every well.

Table 1 shows that none of the water supply wells constructed in 1983 and earlier were more than 250 feet deep, and many of them were capable of producing more than 30 gpm; some had a capacity exceeding 50 gpm. Wells constructed in 2002 and 2006 ranged in depth from 400-800 feet, but did not have a better ratio of success than did shallower wells constructed in preceding years. Both of the 800-foot deep wells did not produce enough water to warrant development as water supply sources.

## **Water Systems/Active Wells**

There are currently four water systems at Catoctin Mountain Park: Headquarters, Blue Blazes, Round Meadow, and the Ike Smith water system. Quarters No. 5 and No. 6 are single family residences that are each supplied by a domestic well.

The Naval Support Facility, Thurmont, operates several wells in the Round Meadow area to supply water for The Presidential Retreat. Information for these wells is not readily available and they are not discussed in this report.

Table 1. Wells in Catoctin Mountain Park

Well Number (MGS)	State Permit Number (well tag no.)	Well Name	Year Const.	Depth feet	Yield, gpm	Use* (2007)
FR-BD-5	---	Jim Brown 0	1936	40	8.5	Abandoned
FR-BD-6	FR-01-8989	Greentop	1955	230	25	Inactive
FR-BD-7	FR-02-1967 FR-02-5349	Misty Mount 1 Deepen MM 1	1956 1956	76 180	3.6	Inactive
FR-BD-8	FR-02-5350	Misty Mount 2	1956	127	24	Inactive
FR-BD-34	FR-03-2795	Blue Blazes 1	1959	230	32	BB/MM
FR-BD-40	FR-66-0492	Poplar Grove 1	1966	180	40	IS
FR-BD-41	FR-66-0489	Poplar Grove 2	1966	160	33	IS
FR-BD-43	FR-66-0490	Jim Brown 1	1966	120	74	RM
FR-BD-44	FR-66-0491	Jim Brown 2	1966	247	8.5	Inactive
FR-BD-49	FR-71-0428	Headquarters	1971	202	19	HQ
FR-BD-114	FR-81-1284	Quarters 5	1983	145	60	SFD
	---	Quarters 6		120		SFD
	FR-94-3010	Jim Brown 3	2002	800	6	Inactive
	FR-94-3011	Jim Brown 4	2002	500	140	RM
	FR-95-0125	Ike Smith Test Hole	2006	800	10	Inactive
	FR-95-0126	Test Hole at Blue Blazes	2006	600	10	Inactive
	FR-95-0303	Blue Blazes 2	2006	660	23	BB/MM
	FR-95-0304	Test Hole at Bldg 167	2006	500	15	Inactive
	FR-95-0305	Ike Smith Well	2006	420	100	IS

MGS (column 1) is Maryland Geological Survey

\* Active water wells in the park supply water to the following water systems:

BB/MM – Blue Blazes, Misty Mount, Visitor Center

IS – Ike Smith water system supplies Owens Creek, Poplar Grove, Chestnut, Greentop

RM – Round Meadow water system

HQ – Park Headquarters

SFD – Single Family Dwelling

## **Headquarters**

Park Headquarters is at the former site of Camp Peniel, an environmental education camp. A well (FR-71-0428) was constructed there in 1971 (Figure 3). It is 202 feet deep. The well has 6-inch steel casing to 30 feet. The annular space outside the casing was sealed with grout to prevent surface water flow flowing into the well and contaminating the well. The well was completed with a 6-inch open borehole from 30-202 feet. Pumping tests determined that the well has a specific capacity of 1½ gpm/foot of drawdown. The well was test pumped for only ¾ hours at rates less than 20 gpm. It was conservatively estimated that the well could reliably produce 20 gpm for several hours. Additional testing would be needed to determine the maximum sustained yield of the well if additional water is needed at the headquarters area (Nutter, 1971).

The well was constructed into the Weverton Formation which is a greenish-gray quartzite and quartz conglomerate that has been compacted and metamorphosed to any of the original granular porosity of the quartz sand. Phyllite (metamorphosed shale) is interbedded with the quartzite. Groundwater occurs in joints, faults, and other fractures in the rock.

## **Blue Blazes**

The Blue Blazes Well No. 1 supplies water to all NPS facilities from the Visitor Center to the Misty Mount Cabins, including the roads and trails maintenance building and two houses (HS-128 and PG-167). A second well was constructed near the maintenance building in August 2006 to supplement the supply from the Blue Blazes Well No. 1. Estimated peak demand for this water system is 9,000 gpd in winter and 12,000 gpd in summer. Well locations are shown in Figure 3. The water system has one 33,000 gallon storage tank at Misty Mount.

The Blue Blazes Well No. 1 (FR-03-2795) was constructed in February 1959 and is 230 feet deep. The well obtains water from fractures in the Catoctin Formation. The well produces 20 gpm with the pump that is currently installed. Trombley and Zynjuk (1985) stated that the well could produce 32 gpm. The well was hydrofracked in the early 1990s, resulting in increasing the yield to about 50 gpm.






Figure 3. Location of the Headquarters and Blue Blazes Wells.

Blue Blazes Well No. 2 (FR-95-0303) was constructed about 750 feet north of the maintenance shop in August 2006. The well is located at the east edge of a clearing, east of an old barn. Water is obtained from fractures in the Catoctin Formation. The well is 660 feet deep and has 8-inch steel casing with a cement grout seal from 0-58 feet. The well is an open borehole from 58-660 feet. The well was test pumped for 25 hours at 23 gpm, causing the water table to draw down from the static water level of 42 feet below ground surface to 155 feet below ground surface. Figure 4 shows the water level response in the well during test pumping and recovery.






Figure 4. Water level drawdown and recovery during testing of Blue Blazes Well No. 2.

## Round Meadow

The Round Meadow water system is supplied by the Jim Brown Wells. There are three inactive wells in the area, which are discussed in a later section of this report. There are two active wells which pump water to two, 33,000-gallon underground tanks. Water is used to supply park service facilities at Round Meadow and the Round Meadow group camp. Well locations are shown on Figure 5.

### ***Jim Brown Well No. 2***

Well FR-66-0490 was constructed in March 1966 and is 120 feet deep. The well obtains water from fractures in the Catoctin Formation. The well has 6-inch casing with a grout seal to a depth of 26 feet. The well is a 6-inch open borehole from 26-120 feet. The well was test pumped for 24 hours at 74 gpm, causing the water level to draw down from the static water level of 29 feet to 70 feet below ground surface.

#### **Jim Brown Well No. 4**

Well FR-94-3011 was constructed in April 2002 and is 500 feet deep. The well obtains water from fractures in the Catocin Formation. The well has 8-inch casing with a grout seal to a depth of 55 feet. The well is an 8-inch open borehole from 55-500 feet. The well was test pumped by airlifting for 3 hours at 100 gpm, causing the water level to draw down from the static water level of 50 feet to 500 feet below ground surface.




Figure 5. Locations of wells for the Round Meadow and Ike Smith water systems.

## **Ike Smith Water System**

The Ike Smith water system is supplied from two wells at the Poplar Grove II group campsite and the new (2006) Ike Smith Well in the Owens Creek Valley (Figure 5). Water from the wells is pumped to the underground storage tank at the Ike Smith pump house and then pumped to two 33,000 gallon storage tanks north of Camp Greentop. Chlorination for water in this system occurs at each well house as water is pumped from the well. Water from this system supplies Camp Greentop, Poplar Grove group camps, Chestnut Picnic area, and Owens Creek campground and picnic area. Peak demand for this water system is less than 15,000 gpd.

### ***Poplar Grove Wells***

There are two water supply wells at the Poplar Grove II group campsite (Figure 5). These wells were constructed in 1966 to replace a surface water source from the Ike Smith Springs.

Well FR-66-0489 was completed in March 1966. It is 160 feet deep and is cased and grouted to a depth of 45 feet. The well is a 6-inch open borehole from 45-160 feet. The well was test pumped for 24 hours at 35 gpm, causing the water level to draw down from the static water level of 55 feet to 86 feet below ground surface.

Well FR-66-0492 was completed in March 1966. It is 180 feet deep and is cased and grouted to a depth of 75 feet. The well is a 6-inch open borehole from 75-160 feet. The well was test pumped for 24 hours at 40 gpm, causing the water level to draw down from the static water level of 60 feet to 85 feet below ground surface.

### ***Ike Smith Well***

Two wells were constructed in the vicinity of Ike Smith Springs in the summer of 2006. The first well (FR-95-0125), which was constructed near the springs and pump house, did not produce much water and was capped. Additional information regarding this well is presented in the “Inactive Wells” section of this report. The second well was located in the Owens Creek valley and produces about 100 gpm. This well (FR-95-0305) will be connected to the Camp Greentop, Poplar Grove, Owens Creek water system.

Well FR-95-0305 was constructed in September 2006. It is located on the east side of the Owens Creek valley, at the intersection of the trail from Ike Smith Springs and the Foxville-Deerfield Road (Figure 5). The well is 420 feet deep and is cased and grouted to a depth of 56 feet. The well is an 8-inch open borehole from 56-420 feet. The well was test pumped for 25 hours at 100 gpm, causing the water level to draw down from the static water level of 17 feet to 75 feet below ground surface. Figure 6 shows the water level response in the well during test pumping and recovery.




Figure 6. Water level drawdown and recovery during testing of the Ike Smith Well.

## Quarters No. 5

The well at Quarters No. 5 (Figure 5) was constructed in 1983 to replace a contaminated spring source. The well is 138 feet deep and 6 inches in diameter. The well was test pumped at 60 gpm for 5 hours, but that pumping rate could not be sustained as the water level in the well was continuing to decline, showing no evidence that the rate of decline was decreasing.

## **Quarters No. 6**

Quarters No. 6 is a single-family home (Figure 5). The well is 120 feet deep and 6 inches in diameter.

## **Inactive Wells**

Several wells in Catoctin Mountain Park are no longer used for one reason or another. Basic data for these wells are included in Table 1. Well completion reports (as available) are included in the appendix of this report. Available information for these wells is summarized in the following sections.

### **Misty Mount/Blue Blazes Area**

There are two inactive wells in the Misty Mount Cabins area (Figure 7). Both wells were located in the north-south trending valley east of the Misty Mount Cabins. The wells were constructed in 1956. Two test wells were drilled in the Blue Blazes area in August and September 2006.

Well FR-02-5349 was constructed in the Winter and Spring of 1956. It was drilled to a depth of 180 feet and produced less than 5 gpm. Water is obtained from fractures in the Catoctin Formation. The well is located east of the creek and about 50 feet north of the entrance road to the Misty Mount Cabins (Figure 7). The well did not produce enough water to warrant installation of a pump. There is no record of it ever being used as a water supply source. Some of the documents in the park files refer to this as Well No. 1 or Well A, as it was the first well drilled in the area.

Well FR-02-5350 was constructed in June 1956. It is located on the east side of the creek and about 300 feet north of Well FR-02-5349 (Figure 7). The well is 127 feet deep and will produce about 25 gpm if its use is limited to about 8 hours per day. Water is obtained from fractures in the Catoctin Formation. The well is on the east side of the creek, and the cabins are on the west side of the creek. Well FR-02-5350 has not been utilized for several years because maintenance of a water line across the creek has always been problematic. However, the well was the sole source of water for the Misty Mount Cabins for many years following its construction until a






Figure 7. Inactive wells in the Misty Mount/Blue Blazes area.

Location of the active Blue Blazes Wells No. 1 & 2 are shown for reference.

new water system was constructed in 1960(?) and water from the Blue Blazes Well was piped into the area. Some of the documents in the park files refer to this as Well No. 2 or Well B, as it was the second well drilled in the area.

Well FR-95-0126 was constructed in August 2006. It is located north of the maintenance shop, about 300 feet south of the communications tower (Figure 7). The well was drilled to a depth of 600 feet in the Catoctin Formation and was pumped dry in 3 hours when pumped at 10 gpm. The well has been capped, and there are no plans to use it.

Well FR-95-0304 was constructed in September 2006. It is located at the end of the driveway, approximately 60 feet southwest of Building 167 (Figure 7). The well was drilled to a depth of 500 feet deep in the Catoctin Formation and was pumped dry in 3 hours when pumped at 15 gpm. The well has been capped, and there are no plans to use it.

### **Ike Smith Springs Area**

Well FR-95-0125 was constructed at Ike Smith Springs in August 2006 (Figure 8). The well is on the north side of the access road to the pump house and east of the creek. The well was drilled to 800 feet and has 8-inch steel casing grouted in place to a depth of 78 feet. The well is an 8-inch open borehole from 78-800 feet. Production was tested by the air-lifting method for 3 hours. The well was estimated to yield 10 gpm. The well was capped and placed in inactive status due to the low estimated yield.

### **Greentop**

A test hole was drilled north of the Central Park Road near the Greentop entrance in 1955 (Figure 8). The well (FR-01-8989) was drilled to 230 feet deep and was test pumped for 24 hours at 25 gpm, resulting in drawdown of about 10 feet below the static water level of 27 feet below ground surface. These data would seem to indicate the well would be a reliable source of water, but there was concern that the well might be constructed in a “pocket” of fractured rock that might be dewatered during long periods of continuous use or during droughts (Otton, 1955). There is no record that the well was ever equipped with a pump or used as for water supply.



## **Jim Brown**

The original well in the Jim Brown area was 40 feet deep and was constructed in 1936. The well was backfilled with concrete and the casing was cut off below ground surface around 1978. The associated concrete storage tank (approximately 15,000 gallons) was removed about 1980. The original Jim Brown Well was no longer needed after construction of the Jim Brown Well No. 2 provided an alternative source of water for facilities at Round Meaadow.

There are two inactive wells in the Jim Brown area (Figure 8).

The Jim Brown Well No.1 (FR-66-0491) was constructed in April 1966. The well was drilled to 250 feet and has 6-inch steel casing grouted in place to a depth of 46 feet. The well is a 6-inch open borehole from 46-250 feet. The well was test pumped at 10 gpm for 9 hours, causing the water level to draw down from the static level of 21 feet to 53 feet below ground level. The well was capped and placed in inactive status due to the low estimated yield. The well is in the middle of the hiking trail (Catoctin Trail) about 350 feet south of the pump house at Jim Brown Well No.2.

The Jim Brown Well No. 3 (FR-94-3010) was constructed in April 2002. The well was drilled to 800 feet and has 8-inch steel casing grouted in place to a depth of 60 feet. The well is an 8-inch open borehole from 60-800 feet. The well was test pumped by airlifting from 800 feet and produced an average of 6 gpm for 3 hours. The static water level was 50 feet below ground surface. The well was capped and placed in inactive status due to the low estimated yield.






Figure 8. Inactive wells in the Ike Smith, Greentop, Jim Brown areas.



## Water Use and Potential for Streamflow Depletion

Firm figures for water use at the park were not available. The estimated peak use (per John Hart, Facility Manager) for the various systems is:

Round Meadow	11,000 gpd
Ike Smith	15,000 gpd
Blue Blazes	12,000 gpd summer 9,000 gpd winter

There are no plans to develop additional facilities at the park, and thus, it's not likely that water use will increase in the future. Usage might decrease as older toilets and showerheads are replaced with low-flow fixtures.

All groundwater has the potential to flow toward, and discharge to, adjacent streams. Pumping groundwater from a well near a stream intercepts some of the groundwater flowing toward the stream, resulting in streamflow depletion. The amount of streamflow depletion is a function of the depth of the well, the distance from the stream, and the degree of interconnection between the stream and groundwater at that particular site. As a worst-case analysis, we can assume a perfect connection between groundwater pumping and streamflow reduction. That is, streamflow is reduced by an amount equal to the rate of groundwater pumping. As an example, we could assume that all of the water demand for the Ike Smith water system is pumped from the new Ike Smith Well adjacent to Owens Creek. Pumping the well continuously at 15,000 gpd is the equivalent of 0.02 cfs. The maximum amount of streamflow depletion from pumping the well is 0.02 cfs.

In reality the impact of groundwater pumping on streamflow is reduced by the return of most of the water to the groundwater system by infiltration through septic leachfields. The numbers given for peak demand represent the maximum pumping from the various wells; demand is much lower on many days. Also, most of the water systems obtain water from a number of wells at various distances from streams. As the volume of water pumped in any given day decreases and the distance from the stream increases, the amount of streamflow depletion decreases.

## Recommended Locations for Well Construction

The strike of geologic formations underlying the park generally follows a NE-SW trend. Many of the stream valleys are oriented along this same trend because it is easier for natural erosion processes to follow the natural fracture patterns in the bedrock than perpendicular to the natural fracture pattern.

The dip of the formations is southeasterly at about 40-50°. A dip of 45 ° would have a slope of 1:1. If we have a situation where a stream valley has formed over a fractured section of the rock units (the fractured rock being more easily erodible), we may have groundwater recharge occurring as infiltration from the stream into the outcrop of the rock. The groundwater could then flow down the dipping slope of the fractured rock and could be intercepted by a well drilled a short distance downgradient (southeast) from the stream. This scenario is shown in the following sketch (Figure 9). Because the dip of the geologic formations is approximately 45°, the rock units underlying the stream will be 100 feet deeper for every 100 feet that the well is located southeast from the stream.




Figure 9. Hydrogeologic model for siting well locations.

It appears that two of the most productive wells, Blue Blazes No. 1 and the new Ike Smith well, fit this hydrogeologic model. However, the Jim Brown No. 4 well does not fit this model and yet produces 100 gpm.

Successful development of water-supply wells at Catoctin is mostly dependent on encountering fracture zones below the water table and the degree to which those fracture zones are interconnected with other water-bearing fractures. It is nearly impossible to conduct surface analyses to determine whether there will be fractures at some depth and even more problematic determining whether those fractures will yield significant amounts of water to a well. The odds of obtaining water from a well can be increased by locating new wells geologically “downgradient” from streams, but it doesn’t guarantee success.

The seemingly random pattern of fracturing in the bedrock at Catoctin can readily be illustrated by looking at past well drilling. Four deep (400-800 feet) wells have been drilled in the vicinity of the Jim Brown Wells (Figures 5 & 8). Two of these wells produce large amounts of water (75-100 gpm), and two of the wells produce less than 10 gpm. At Misty Mount, two wells were drilled in the same geologic setting, the bottom of the valley east of the creek (Figure 7). One of the wells produced 25 gpm, and the other produced 3 gpm.

## **Typical Well Construction**

Typical construction for wells at Catoctin Mountain Park is shown in Figure 10. An oversize borehole (usually 12-14 inches diameter) is drilled through the soil and weathered bedrock comprising the regolith, penetrating several feet into bedrock. Well casing (6-8 inch inside diameter) is placed in the hole, and the annular space is filled with cement grout to form a surface seal to prevent downward flow of surface water into the borehole. The well is completed by drilling an uncased, open borehole into the fractured bedrock. Generally, the well casing and cement grout seal extends to about 40-60 feet below ground surface. Wells drilled prior to 2002 were generally no more than 200-250 feet total depth. Wells drilled in 2002 and later range from 400-800 feet deep.




Figure 10. Typical well construction at Catoctin Mountain Park.

## Recommendations

Some of the inactive wells in the park could function as low-yield, supplemental supply wells. Constructing a well in this type of geologic environment that will yield more than 20 gpm should be considered unusual. It's much more likely that a well drilled in fractured metamorphic rock would yield less than 10 gpm. A 10 gpm well operated on a schedule of 8 hours on and 16 hours off will produce nearly 5,000 gpd. A couple of low-yield wells and adequate storage tanks can result in a viable water system.

Some of the previously constructed, and currently inactive, wells might be very good supply wells. For example, the well at Greentop was reportedly test pumped at 25 gpm for 24 hours

with only 10 feet of drawdown. This would seem to indicate that it would be a very good well, but it has never been utilized. Before more wells are drilled at the park, records should be reviewed and existing inactive wells should be tested to determine whether they might meet the need.

Water levels in the existing wells should be measured on a regular basis to monitor water table changes in response to groundwater pumping, natural seasonal cycles, and drought effects. These data can also be used to identify problems with the pump or piping in a well. Often when a well stops pumping water or the pumping rate decreases, the first reaction is that the well must have gone dry, or is going dry. It's more likely that the pump is wearing out and pumps less efficiently, or there is a leak somewhere in the piping. Regular water-level monitoring will help diagnose production problems by identifying whether the problem lies with the pumping equipment or with the aquifer. Quarterly water level monitoring would be optimal; semiannual monitoring should be considered the minimum amount of data needed.

Anticlinorium – A regional anticlinal structure that may include smaller anticlines and synclines. A sketch of the Catoctin Mountain anticlinorium from Whitaker (1955) is shown below.




FIGURE 2.—SOUTH MOUNTAIN FOLD  
After Cloos (1947, p. 857)

Metabasalt – A basalt that has undergone metamorphism. Often called greenstone.

Metarhyolite – Rhyolitic rock that has undergone metamorphism. The metarhyolite at Catoctin has a bluish or bluish-gray hue.

Phyllite – A metamorphic rock similar to schist but finer grained, so that the constituent grains cannot be seen with the unaided eye. Phyllite is considered to be a product of low-grade metamorphism. It is transitional between slate and schist.

Regolith – The regolith is everything from land surface down to solid bedrock. It includes soil and partially weathered rock overlying bedrock.

## Literature Cited

Dine, James R., Michael D. Tompkins, and Mark T. Duigon, 1985, *Ground-Water and Surface-Water Data For Frederick County, Maryland*, Maryland Geological Survey Basic Data Report No. 15, 240 pp.

Duigon, M.T., and J.R. Dine, 1987, *Water Resources of Frederick County, Maryland*, Bulletin #33 Maryland Geological Survey, Maryland Department of Natural Resources, Annapolis, MD, 106 pp.

Fauth, J.L., 1977, *Geologic Map of the Catoctin Furnace and Blue Ridge Summit Quadrangles, Maryland*, Maryland Geological Survey, Annapolis, MD, 1 sheet.

Huth Engineers Inc. and R.E. Wright Associates Inc., 1981, *Hydrogeology Study Catoctin Mountain Park, Maryland*, consultants report to National Park Service, 82 pp.

Nutter, Larry J., 1971, *Ground-Water Supply at Camp Peniel, Catoctin Mountain Park, Maryland*, U.S. Geological Survey administrative report, 5 pp.

Otton, E.G., 1955, *Memorandum on present status of the ground-water supply at Catoctin National Park, Camps No. 2 and 3, Thurmont, MD*, unpublished memo by U.S. Geological Survey dated July 12, 1955, 4 pages.

Trombley, Thomas J, and Linda D. Zynjuk, 1985, *Hydrogeology and Water Quality of the Catoctin Mountain National Park Area, Frederick County, Maryland*, U.S. Geological Survey Water-Resources Investigation Report 85-4241, 41 pp.

Southworth, Scott, and Danielle Denenny, 2006, *Geologic Map of the National Parks in the National Capitol Region, Washington, D.C., Virginia, Maryland, and West Virginia*, U.S. Geological Survey Open-File Report 2005-1331, 266 pp. & 1 plate.

Whitaker, John C., 1955, *Geology of Catoctin Mountain*, Bulletin of Geological Society of America, vol. 66, pp. 436-462



## Appendix

### Well Completion Reports

Wells are listed in order of construction, oldest well first.

Greentop Well	1955
Misty Mount No. 1	1955
Deepen Misty Mount No. 1	1956
Misty Mount No. 2	1956
Blue Blazes No. 1	1958
Poplar Grove No. 1	1966
Poplar Grove No. 2	1966
Jim Brown No. 1	1966
Jim Brown No. 2	1966
Headquarters Well	1971
Quarters No. 5	1983
Jim Brown No. 3	2002
Jim Brown No. 4	2002
Ike Smith Test Hole	2006
Test Hole at Blue Blazes	2006
Blue Blazes No. 2	2006
Test Hole at Bldg. 167	2006
Ike Smith Well	2006



STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES  
The Johns Hopkins University  
BALTIMORE 18, MARYLAND

GreenTop Well

## APPLICATION FOR PERMIT TO DRILL WELL

An application must be submitted and permit received before drilling a well

Owner Antomac River Naval Command  
Street or R. F. D. Box 232 Gallatin St., N.W.  
Post Office Washington 25, D.C.

Driller Columbia Pump & Well Co.  
Street or R. F. D. 232 Gallatin St., N.W.  
Post Office Washington 11, D.C.  
Date April 29, 1955

Quantity of Water Needed (G. P. M.) 20  
Use for Water General Use  
Approximate Depth of Well (feet) 250  
Method of Drilling to be used Cable-Tool

Location of Well  
County Fredrick  
Nearest Town Thurmont, Maryland  
Distance from Town approx 6 mile  
Direction from Town West

## PERMIT TO DRILL WELL

(Permit to be returned to Driller)

NOT TO BE FILLED IN BY DRILLER

Permit No. 18989

Samples of Cuttings (Yes)  
Required by Department (No)

Owner Requires Permit (Yes)  
to Appropriate Water (No)

Owner Has Permit (Yes)  
to Appropriate Water (No)

The applicant is herewith granted a permit to drill this well subject to the conditions stipulated.

James H. Simpson  
Director

Date May 2, 1955

Special conditions that may apply:

roads & streams to be  
closed for military  
purposes. 050255

Sample sacks furnished by  
U.S.G.S.

Permit issued National Park Service (ORIGINAL)  
2/18/55

## Description of Location of Well


(This information should be definite enough to permit locating well on a county map)

Near what road Catoctin National Park

On which side of road North  
(North, East, South, West)

Distance from road 3/4 mile

Draw a sketch below showing location of well in relation to nearby towns, roads and streams with north in the direction of the arrow.



FR018989  
This report

CES  
060755  
230

28

Form 4

STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES

The Johns Hopkins University  
BALTIMORE 18, MARYLAND

Misty Mount No. 1

## APPLICATION FOR PERMIT TO DRILL WELL

An application must be submitted and permit received before drilling a well

Owner CATOCCH MOUNTAIN PARK  
NATIONAL PARK SERVICE INDEPENDENT  
Driller Clavin R. Smith  
Street or R. F. D. Smithsburg Md.  
Post Office Smithsburg Md.  
Post Office THURMONT ORDER NO 15-952 Date Dec 16, 55

Quantity of Water Needed (G.P.M.) 5  
Use for Water Camp  
Approximate Depth of Well (feet) 150  
Method of Drilling to be used Keystone  
Location of Well  
County Fredrick  
Nearest Town THURMONT  
Distance from Town 3 miles  
Direction from Town West

## PERMIT TO DRILL WELL

(Permit to be returned to Driller)

NOT TO BE FILLED IN BY DRILLER

Permit No. 21967

Samples of Cuttings ☒ Yes  
Required by Department ☒ No

Owner Requires Permit ☒ Yes  
to Appropriate Water ☒ No

Owner Has Permit ☒ Yes  
to Appropriate Water ☒ No

The applicant is herewith granted a permit to drill this well subject to the conditions stipulated.

John P. Reinhardt  
Director

Date January 17, 1956

Special conditions that may apply:


Owner's permit issued 1/17/56

011756

Description of Location of Well  
(This information should be definite enough to permit locating well on a county map)

Near what road TOXSVILLE TO THURMONTOn which side of road NORTH  
(North, East, South, West)Distance from road 1/2 mile Camp

Draw a sketch below showing location of well in relation to nearby towns, roads and streams with north in the direction of the arrow.



(DUPLICATE)

Form 5

110124

STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES  
The Johns Hopkins University  
BALTIMORE 18, MARYLAND

FR021967

## WELL COMPLETION REPORT

This report must be submitted within 30 days after completion of the well

43 WELL DESCRIPTION				Permit Number <u>21967</u>	
WELL LOG		CASING AND SCREEN RECORD			
State the kind of formations penetrated, their depth, their thickness, and if water-bearing		State the kind and size of casing, liner, shoe, screen, and other accessories (if no casing used, give diameter of well)			
FEET		DIAM.		FEET	
from ..... to .....		(inches)		from ..... to .....	
Earth	0 - 5'	8"	0 - 17 1/2'	<p><b>PUMPING TEST</b></p> <p>Hours Pumped <u>4</u></p> <p>Type of Pump Used <u>Hand</u></p> <p>Pumping Rate</p> <p>Gallons per Minute <u>11</u></p> <hr/> <p><b>WATER LEVEL</b></p> <p>Distance from land surface to water:</p> <p>Before Pumping <u>64</u> Ft.</p> <p>When Pumping <u>64</u> Ft.</p> <hr/> <p><b>APPEARANCE OF WATER</b></p> <p>Clear .....</p> <p>Cloudy <input checked="" type="checkbox"/></p> <p>Taste .....</p> <p>Odor .....</p> <hr/> <p>Height of Casing Above Land Surface <u>2</u> Ft.</p> <hr/> <p><b>PUMP INSTALLED</b></p> <p>Type .....</p> <p>Capacity</p> <p>Gallons per Minute .....</p> <p>Gallons per Hour .....</p> <p>Pump Column Length .....</p> <hr/> <p><b>REMARKS</b></p> <p><i>This well was not finished by me. Found by another well working a bit.</i></p> <hr/> <p>Well Was Completed</p> <p>Date <u>Nov 1, 1967</u></p> <p>Well Driller</p> <p style="text-align: right;">Signature</p>	
Mud	5 - 30	6"	0 - 42 1/2'		
Rock	30 - 42				
Water bearing at 42' 5" to 51'	42 - 51				
Rock	51 - 76				

EX POST FACTO Filing 25347

Form 4

STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES

The Johns Hopkins University  
BALTIMORE 18, MARYLAND

Deepen  
Misty Mount No. 1

FR 25349

APPLICATION FOR PERMIT TO DRILL WELL

An application must be submitted and permit received before drilling a well

Owner Catoctin Natl Park Service Driller William Miller  
Street or R. F. D. EMMITTSBURG, MD  
Post Office THURMONT, Md Date 11/8/56

Quantity of Water Needed (G. P. M.) 10 Location of Well  
Use for Water PARK Public Service County FREDERICK  
Approximate Depth of Well (feet) 180' Nearest Town THURMONT  
Method of Drilling to be used CABLE TOOLS Distance from Town 3.5  
CHURN DRILL Direction from Town West

PERMIT TO DRILL WELL

(Permit to be returned to Driller)

NOT TO BE FILLED IN BY DRILLER

Permit No. 25349

Samples of Cuttings ☒ Yes  
Required by Department ☒ No

Owner Requires Permit ☒ Yes  
to Appropriate Water ☒ No

Owner Has Permit ☒ Yes  
to Appropriate Water ☒ No

The applicant is herewith granted a permit to drill this well subject to the conditions stipulated.

James T. Thompson  
Director

Date November 13, 1956

Special conditions that may apply:

See P21,967 for part of hole drilled by Elvin R. Smith.


Description of Location of Well  
(This information should be definite enough to permit locating well on a county map)

Near what road APPROXIMATELY 2500'  
N.E. PARK OFFICE

On which side of road ON LEFT OR WEST SIDE  
(North, East, South, West)

Distance from road 90' FROM PARK DRIVE

Draw a sketch below showing location of well in relation to nearby towns, roads and streams with north in the direction of the arrow.



this is NOT TO SCALE  
ROADS ARE ONLY  
GENERAL DIRECTIONS

(ORIGINAL)

Form 5

## EX Post FACTO FILING Well #1

STATE OF MARYLAND

DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES

The Johns Hopkins University  
BALTIMORE 18, MARYLAND

FR 25349

## WELL COMPLETION REPORT

This report must be submitted within 30 days after completion of the well

76 WELL DESCRIPTION				Permit Number 25349
WELL LOG State the kind of formations penetrated, their depth, their thickness, and if water-bearing		CASING AND SCREEN RECORD State the kind and size of casing, liner, shoe, screen, and other accessories (if no casing used, give diameter of well)		Name of Owner Catoctin Nat. Park Service
HARD CONGLOMERATE	FEET 76	6"	DIAM. (inches)	PUMPING TEST
	from 0 to 180			FEET from to
LENGTH OF CASING MAY HAVE BEEN FILED by ELVIN R. SMITH PERMIT # 21967, NOT COMPLETED, BUT DRILLED DEEPER by Kohl Bros.				Hours Pumped 24
				Type of Pump Used Plunger
				Pumping Rate Gallons per Minute 3.6
				WATER LEVEL
				Distance from land surface to water:
				Before Pumping 0 Ft.
				When Pumping 168 Ft.
				APPEARANCE OF WATER
				Clear CLEAR
				Cloudy
				Taste
				Odor
				Height of Casing Above Land Surface 1 Ft.
				PUMP INSTALLED
				Type Well
				Capacity ABANDONED BUT
				Gallons per Minute
				Gallons per Hour CAPTION
				Pump Column Length Ft.
REMARKS				
Well Was Completed				
Date APR. 19, 1956				
Well Driller Wm. Miller				
Per Kohl Bros., Richard D. Kohl				
Signature				



EX POST FACTO FILING

25350

STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES  
The Johns Hopkins University  
BALTIMORE 18, MARYLAND

Misty Mount No. 2

FR 25350

## APPLICATION FOR PERMIT TO DRILL WELL

An application must be submitted and permit received before drilling a well

Owner CATOCIN NATL PARK SERVICE Driller William Miller  
Street or R. F. D. EMMITTSBURG, MD  
Post Office THURMONT, MD Date 11/8/56

Quantity of Water Needed (G.P.M.) 10 Location of Well  
Use for Water PARK PUBLIC SERVICE County FREDERICK  
Approximate Depth of Well (feet) 127' Nearest Town THURMONT  
Method of Drilling to be used CABLE TOOLS Distance from Town 3.6  
CHURN DRILL Direction from Town West

## PERMIT TO DRILL WELL

(Permit to be returned to Driller)

NOT TO BE FILLED IN BY DRILLER

Permit No. 25350Samples of Cuttings { Yes  
Required by Department { NoOwner Requires Permit { Yes  
to Appropriate Water { NoOwner Has Permit { Yes  
to Appropriate Water { No

The applicant is herewith granted a permit to drill this well subject to the conditions stipulated.

*[Signature]*  
Director

Date November 13, 1956

Special conditions that may apply:


111356

## Description of Location of Well

(This information should be definite enough to permit locating well on a county map)

Near what road APPROXIMATELY 3000'  
N. OF PARK OFFICEOn which side of road LEFT OR WEST SIDE  
(North, East, South, West)Distance from road 100' FROM PARK DRIVE

Draw a sketch below showing location of well in relation to nearby towns, roads and streams with north in the direction of the arrow.



THIS IS NOT TO SCALE  
ROADS ARE ONLY  
GENERAL DIRECTIONS

(ORIGINAL)

Form 5

EX POST FACTO

STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES  
The Johns Hopkins University  
BALTIMORE 18, MARYLAND

243  
871156

FR 25354

## WELL COMPLETION REPORT

This report must be submitted within 30 days after completion of the well

WELL DESCRIPTION			Permit Number 25350
<b>WELL LOG</b> State the kind of formations penetrated, their depth, their thickness, and if water-bearing		<b>CASING AND SCREEN RECORD</b> State the kind and size of casing, liner, shoe, screen, and other accessories (if no casing used, give diameter of well)	
<b>OVERBURDEN</b> 0' - 15' <b>HARD</b> <b>CONGLOMERATE</b> 15' to 127' <b>FAULTED</b> at 65'	<b>FEET</b> from ..... to .....	<b>CASING</b> 6" (inches) <b>CEMENT</b> <b>GROUT POURED</b> <b>AROUND 6"</b> <b>CASIN FILLING</b> <b>AREA MADE</b> <b>by 8" Bit to</b> <b>28'</b>	<b>FEET</b> from ..... to .....
		<b>PUMPING TEST</b> Hours Pumped 24 Type of Pump Used PLGR Pumping Rate Gallons per Minute 24	
		<b>WATER LEVEL</b> Distance from land surface to water: Before Pumping 0' F When Pumping 105' F	
		<b>APPEARANCE OF WATER</b> Clear CLEAR Cloudy Taste Odor	
		Height of Casing Above Land Surface 1' F	
		<b>PUMP INSTALLED</b> Type SUBMERSIBLE Capacity Gallons per Minute 20 Gallons per Hour 1200 Pump Column Length 105'	
		<b>REMARKS</b> 1st WATER 40' 2nd WATER 65' BALANCE OF WELL APPARENTLY, NO MORE WATER	
		Well Was Completed Date JULY 11, 1956 Well Driller Wm. Miller per Kohl Bros Richard L. Kohl Signature	

STATE OF MARYLAND  
DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES

The Johns Hopkins University  
BALTIMORE 18, MARYLAND

Blue Blazes No. 1

FR 32795

## APPLICATION FOR PERMIT TO DRILL WELL

An application must be submitted and permit received before drilling a well

Owner NATIONAL PARK SERVICE Driller WILLIAM MILLER  
HARRISBURG'S KOHL BROTHERS  
Street or R. F. D. CATOCTIN MT. PARK Street or R. F. D. 2154 GREENWOOD  
Post Office THURMONT MD Post Office HARRISBURG PA  
Date 11/3/58

Quantity of Water Needed (G.P.M.) 20 Location of Well  
Use for Water DOMESTIC County FREDERICK  
Approximate Depth of Well (feet) 200' Nearest Town THURMONT  
Method of Drilling to be used CHURN Distance from Town 3 MI  
Direction from Town N.W.

## PERMIT TO DRILL WELL

(Permit to be returned to Driller)

NOT TO BE FILLED IN BY DRILLER

Permit No. 32795

Samples of Cuttings ☒ Yes  
Required by Department ☒ No

Owner Requires Permit ☒ Yes  
to Appropriate Water ☒ No

Owner Has Permit ☒ Yes  
to Appropriate Water ☒ No

The applicant is herewith granted a permit to drill this well subject to the conditions stipulated.

Joseph T. Ingewald  
Director

Date November 7, 1958


Special conditions that may apply:

Owner's permit issued 2/17/55116758

Description of Location of Well  
(This information should be definite enough to permit locating well on a county map)

Near what road Rt 77On which side of road NORTH  
(North, East, South, West)Distance from road 300'

Draw a sketch below showing location of well in relation to nearby towns, roads and streams with north in the direction of the arrow.



(ORIGINAL)

DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES

DELAyED REpORT Filed 6/26/89-4-51  
STATE OF MARYLAND

STATE OF MARYLAND

DEPARTMENT OF GEOLOGY, MINES AND WATER RESOURCES

The Johns Hopkins University  
BALTIMORE 18, MARYLAND

FRØ 32795

## WELL COMPLETION REPORT

This report must be submitted within 30 days after completion of the well

230

[illegible]

FREDERICK COUNTY DEPARTMENT OF HEALTH  
12 East Church Street  
Winchester Hall  
Frederick, Maryland

Poplar Grove No. 1

Completed by well driller. Copy to be sent to the Frederick County Health  
Department within fifteen (15) days after completion of drilling.

HEALTH DEPARTMENT COMPLETION CERTIFICATE FOR PRIVATE WELLS

Date March 28, 1966

Owner of Property Catoctin Mountain Park Driller York Drilling Company, Inc. Reider  
Roosevelt Avenue Opposite Lincoln Park  
Address Thurmont, Maryland Address York, Pennsylvania 17405

Exact location of property where well was drilled Foxville, on the Manahan Road, beyond the Jot  
Corps Camp No. 4 well - 400' west.

If Subdivision: Name \_\_\_\_\_ Block No. \_\_\_\_\_ Lot No. \_\_\_\_\_

Permit No. F-66-W-492 (This is the number issued by the Department of Geology.)

Construction and performance characteristics of well

- (1) Diameter of largest bit 8"
- (2) Ground water encountered at None ft.
- (3) At what depth was first water encountered 95 ft. Cased off: Yes \_\_\_\_\_ No. X
- (4) Total depth of well 180 ft. Standing water level in well below ground surface when  
pumped 87 ft.
- (5) Casing: Diameter 6" ID Length of metal casing 76'  
Are casing joints watertight? Yes XX No. \_\_\_\_\_ How were these joints sealed:  
by welding XX  
by treaded sleeve \_\_\_\_\_  
Finished casing terminates 1½ ft. above ground level 74½ ft below ground level
- (6) Well cement grouted: Yes XX No. \_\_\_\_\_ To what depth 74½ ft.  
(If answer to No. 6 is NO an acceptable explanation in detail is necessary \_\_\_\_\_)

(7) Yield of well: 40 gal. per min. No. of hours pump operated at this rate during  
test 24 hours \_\_\_\_\_ minutes.

(8) Log of materials encountered during drilling Burden, green rock, brown shale and sandstone

I hereby certify that the above information concerning this well is true and correct.

C. H. Reider  
Well Driller  
Dept. of Geology, Mines and Water  
Resources  
License No. 92

THIS REPORT  
MUST BE SUBMITTED  
WITHIN 30 DAYS  
AFTER COMPLETION  
OF THE WELL

## WELL COMPLETION REPORT

## WELL DESCRIPTION

## WELL LOG

State the kind of formations penetrated, their color, their depth, their thickness, and if water-bearing

### CASING AND SCREEN RECORD

State the kind and size and position of casing, liner, shoe, screen, and other accessories (if no casing used, give diameter of well).

Permit Number B-66-K-492

Owner Catoctin Mountain

Address ~~Thurmont~~ Maryland

Subdivision \_\_\_\_\_

Section \_\_\_\_\_ Lot \_\_\_\_\_

## PUMPING TEST

Hours Pumped 24 hoursType of Pump Used Submersible

Pumping Rate \_\_\_\_\_

Gallons per Minute 40

## WATER LEVEL

Distance from land surface to water:

Before Pumping 60 Ft.

When Pumping 85 Ft.

APPEARANCE OF WATER

Clear XX Cloudy       

Taste None

Odor None

Height of Casing Above Land

Surface 18<sup>17</sup> Ft.

PUMP INSTALLED

Type \_\_\_\_\_

Capacity


Gallons per Minute \_\_\_\_\_

Gallons per Hour \_\_\_\_\_

Pump Column Length \_\_\_\_\_ Ft.

## LOCATION OF WELL ON LOT

Show permanent structures such as building(s), septic tank, and/or other landmarks and indicate not less than 2 distances (measurements) to well.



Date Well

Was Completed 3/9/66

Well Driller C. N. REIDEN

Signature C. H. Railor

**TRIPPLICATE**



THE FREDERICK COUNTY DEPARTMENT OF HEALTH  
12 East Church Street  
Winchester Hall  
Frederick, Maryland

Poplar Grove No. 2

NOTE-- To be completed by well driller. Copy to be sent to the Frederick County Health Department within fifteen (15) days after completion of drilling.

HEALTH DEPARTMENT COMPLETION CERTIFICATE FOR PRIVATE WELLS

Date March 28, 1966

Owner of Property Catoctin Mountain Park Driller York Drilling Company, Inc. Reider  
Roosevelt Avenue Opposite Lincoln Park  
Address Thurmont, Maryland Address York, Pennsylvania 17405

Exact location of property where well was drilled Foxville, on the Manahan Road, beyond the Job Corps Camp No. 3 well 300' west

If Subdivision: Name \_\_\_\_\_ Block No. \_\_\_\_\_ Lot No. \_\_\_\_\_

Permit No. F-66-W-489 (This is the number issued by the Department of Geology.)

Construction and performance characteristics of well

- (1) Diameter of largest bit 8"
- (2) Ground water encountered at None ft.
- (3) At what depth was first vein water encountered 59 ft. Cased off: Yes \_\_\_\_\_ No. X
- (4) Total depth of well 160 ft. Standing water level in well below ground surface when pumping 85 ft.
- (5) Casing: Diameter of casing 6" I.D. Length of metal casing 46  
Are casing joints watertight? Yes XX No. \_\_\_\_\_ How were these joints sealed:  
by welding XX  
by treaded sleeve \_\_\_\_\_  
Finished casing terminates 44½ ft. above ground level 1½ ft below ground level
- (6) Well cement grouted: Yes XX No \_\_\_\_\_ To what depth 44½ ft.  
(If answer to No. 6 is NO an acceptable explanation in detail is necessary \_\_\_\_\_)

(7) Yield of well: 35 gal. per min. No. of hours pump operated at this rate during test 24 hours \_\_\_\_\_ minutes.

(8) Log of materials encountered during drilling Burden, Blue and green rock, brown shale and gravel

I hereby certify that the above information concerning this well is true and correct.

C. H. Reider  
Well Driller  
Dept. of Geology, Mines and Water Resources  
License No. 92

MUST BE SUBMITTED  
WITHIN 30 DAYS  
AFTER COMPLETION  
OF THE WELL

WELL COMPLETION REPORT

WELL DESCRIPTION

**WELL LOG**  
State the kind of formations penetrated, their color, their depth, their thickness, and if water-bearing

**CASING AND SCREEN RECORD**  
State the kind and size and position of casing, liner, shoe, screen, and other accessories (if no casing used, give diameter of well).

	FEET from 0 to	
BURDEN	37'	
Hard Blue Rock	45'	
" Green "	58'	
Damp Gravel	59'	
Hard Green Rock	73'	
Brown Shale	74'	
Gravel & Brown Shale	78'	water
Soft Green & Brown Shale	87'	
Green Rock	107'	
Brown Shale & Gravel	110'	
Hard Blue & Green Rock	160'	

DIAM.  
(inches)  
6"  
Schedule  
40  
Pipe  
welded

44' 6"

Permit Number F-66-W-48  
Owner Catoctin Mountain  
Address Thurmont, Maryland  
Subdivision \_\_\_\_\_  
Section \_\_\_\_\_ Lot \_\_\_\_\_

**PUMPING TEST**  
Hours Pumped 24  
Type of Pump Used Submersible  
Pumping Rate 35  
Gallons per Minute 35


**WATER LEVEL**  
Distance from land surface to water:  
Before Pumping 55 F  
When Pumping 86 F

**APPEARANCE OF WATER**  
Clear XX Cloudy \_\_\_\_\_  
Taste None  
Odor None

Height of Casing Above Land  
Surface 18" F

**PUMP INSTALLED**  
Type \_\_\_\_\_  
Capacity \_\_\_\_\_  
Gallons per Minute \_\_\_\_\_  
Gallons per Hour \_\_\_\_\_  
Pump Column Length \_\_\_\_\_ F

**LOCATION OF WELL ON LOT**  
Show permanent structures such as building(s), septic tank, and/or other landmarks and indicate not less than 2 distances (measurements) to well.



Date Well Completed 3/14/66  
Well Driller C. H. REIDER  
Signature C. H. Reider

TRIPLICATE

THE FREDERICK COUNTY DEPARTMENT OF HEALTH  
12 East Church Street  
Winchester Hall  
Frederick, Maryland

Jim Brown No. 1

To be completed by well driller. Copy to be sent to the Frederick County Health Department within fifteen (15) days after completion of drilling.

HEALTH DEPARTMENT COMPLETION CERTIFICATE FOR PRIVATE WELLS

Date April 5, 1966

Owner of Property Catoctin Mountain Park Driller York Drilling Company, Inc. C. Reider

Roosevelt Avenue Opposite Lincoln Park

Address Thurmont, Maryland

Address York, Pennsylvania 17405

Exact location of property where well was drilled Foxville, on the Manahan Road, beyond the Job

Corps Camp No. 1 Well -- 1,100 ft. west of Manahan Road - Chestnut Camp Site.

If Subdivision: Name \_\_\_\_\_ Block No. \_\_\_\_\_ Lot No. \_\_\_\_\_

Permit No. F-66-W-490 (This is the number issued by the Department of Geology.)

Construction and performance characteristics of well

(1) Diameter of largest bit 8"

(2) Ground water encountered at \_\_\_\_\_ ft.

(3) At what depth was first vein water encountered 28 ft. Cased off: Yes \_\_\_\_\_ No. xx

(4) Total depth of well 120 ft. Standing water level in well below ground surface when pumping 74 ft.

(5) Casing: Diameter 6" Length of metal casing 27

Are casing joints watertight? Yes xx No. \_\_\_\_\_ How were these joints sealed:

by welding xx

by treaded sleeve \_\_\_\_\_

Finished casing terminates 1½ ft. above ground level 25½ ft below ground level

(6) Well cement grouted: Yes xx No \_\_\_\_\_ To what depth 25½ ft.  
(If answer to No. 6 is NO an acceptable explanation in detail is necessary \_\_\_\_\_)

(7) Yield of well: 74 gal. per min. No. of hours pump operated at this rate during test 24 hours 0 minutes.

(8) Log of materials encountered during drilling Hard grey and blue rock interbedded with gravel veins

I hereby certify that the above information concerning this well is true and correct.

C. H. Reider  
Well Driller  
Dept. of Geology, Mines and Water  
Resources

License No. 92

State Office Building  
ANNAPOLIS, MARYLAND 21401

STATE OF MARYLAND  
DEPARTMENT OF  
WATER RESOURCES

Well #1

THIS REPORT  
MUST BE SUBMITTED  
WITHIN 30 DAYS  
AFTER COMPLETION  
OF THE WELL

WELL COMPLETION REPORT

WELL DESCRIPTION

**WELL LOG**  
State the kind of formations penetrated, their color, their depth, their thickness, and if water-bearing

**CASING AND SCREEN RECORD**  
State the kind and size and position of casing, liner, shoe, screen, and other accessories (if no casing used, give diameter of well).

	FEET from 0 to		DIAM. (inches)	FEET from 0 to
Burden		10'	6" I.D.	
Hard Grey Rock		28'	Steel	25 1/2'
Gravel - water		32'		
Grey & Blue Rock		39'		
Brown Rock & Gravel - water		41'		
Brown & Blue Rock		71'		
WATER		74'		
Gravel - water		77'		
Hard Blue Rock		100'		
Quartz		110'		
Hard Green Rock		120'		

Permit Number F-66-W-490  
Owner Catoctin Mountain Park  
Address Thurmont, Maryland  
Subdivision \_\_\_\_\_  
Section \_\_\_\_\_ Lot \_\_\_\_\_

**PUMPING TEST**  
Hours Pumped 24  
Type of Pump Used Submersible  
Pumping Rate 74 Gal. Per. Min.  
Gallons per Minute 74


**WATER LEVEL**  
Distance from land surface to water:  
Before Pumping 29 Ft.  
When Pumping 70 Ft.

**APPEARANCE OF WATER**  
Clear XX Cloudy \_\_\_\_\_  
Taste None  
Odor None

Height of Casing Above Land  
Surface 1 1/2 Ft.

**PUMP INSTALLED**  
Type \_\_\_\_\_  
Capacity  
Gallons per Minute \_\_\_\_\_  
Gallons per Hour \_\_\_\_\_  
Pump Column Length \_\_\_\_\_ Ft.

**LOCATION OF WELL ON LOT**  
Show permanent structures such as building(s), septic tank, and/or other landmarks and indicate not less than 2 distances (measurements) to well.



Date Well  
Was Completed 3-29-66

Well Driller C.H. Reider  
Signature C.H. Reider

12 East Church Street  
Winchester Hall  
Frederick, Maryland

Jim Brown No. 2

NOTE-- To be completed by well driller. Copy to be sent to the Frederick County Health Department within fifteen (15) days after completion of drilling.

HEALTH DEPARTMENT COMPLETION CERTIFICATE FOR PRIVATE WELLS

Date May 19, 1966

Owner of Property Catoctin Mountain Park Driller York Drilling Company, Inc. C. Reider  
Address Thurmont, Maryland Address Roosevelt Avenue Opposite Lincoln Park  
York, Pennsylvania 17404

Exact location of property where well was drilled Foxville, on the Manahan Road beyond the Job  
Corps Camp No. 2 Well - 1,000 ft. west.

If Subdivision: Name \_\_\_\_\_ Block No. \_\_\_\_\_ Lot No. \_\_\_\_\_

Permit No. F-66-W491 (This is the number issued by the Department of Geology.)

Construction and performance characteristics of well

- (1) Diameter of largest bit 8"
- (2) Ground water encountered at 28 ft.
- (3) At what depth was first water encountered 53 ft. Cased off: Yes \_\_\_\_\_ No XX
- (4) Total depth of well 250 ft. Standing water level in well below ground surface when \_\_\_\_\_ ft.
- (5) Casing: Diameter 6" Length of metal casing 46  
Casing joints watertight? Yes XX No \_\_\_\_\_ How were these joints sealed:  
by welding XX  
by treaded sleeve \_\_\_\_\_  
Finished casing terminates 1 1/2 ft. above ground level 44 1/2 ft below ground level
- (6) Well cement grouted: Yes XX No \_\_\_\_\_ To what depth 44 1/2 ft.  
(If answer to No. 6 is NO an acceptable explanation in detail is necessary \_\_\_\_\_)
- (7) Yield of well: 10 gal. per min. No. of hours pump operated at this rate during  
test 9 hours: 15 minutes.
- (8) Log of materials encountered during drilling Clay, Sand, Hard Blue Rock, Broken Formation

I hereby certify that the above information concerning this well is true and correct.

C. H. Reider  
Well Driller  
Dept of Geology, Mines and Water  
Resources  
License No. 92

$$\begin{aligned}
 & \frac{1}{2} \int_{\mathbb{R}^n} |\nabla u|^2 dx \\
 & = \frac{1}{2} \int_{\mathbb{R}^n} |\nabla u|^2 dx + \frac{1}{2} \int_{\mathbb{R}^n} |\nabla u|^2 dx \\
 & = \frac{1}{2} \int_{\mathbb{R}^n} |\nabla u|^2 dx + \frac{1}{2} \int_{\mathbb{R}^n} |\nabla u|^2 dx
 \end{aligned}$$



THE FREDERICK COUNTY DEPARTMENT OF HEALTH  
12 East Church Street  
Winchester Hall  
Frederick, Maryland

Headquarters Well

RE -- To be completed by well driller. Copy to be sent to the Frederick County Health Department within fifteen (15) days after completion of drilling.

HEALTH DEPARTMENT COMPLETION CERTIFICATE FOR PRIVATE WELLS

Date 4-3-71  
Owner of Property Dept. of Interior Driller AUSTIN R. KEYSER, INC.  
Address Natl. Park Serv., Wash. DC Address WELL DRILLING  
RT. 7, FREDERICK, MD.  
MO 2-1949  
Exact location of property where well was drilled located on land b  
Co. near town of Thurmont  
If Subdivision: Name \_\_\_\_\_ Block No. \_\_\_\_\_ Lot No. \_\_\_\_\_  
Permit No. FR-71-0428 (This is the number issued by the Department of Geology.)

Construction and performance characteristics of well

- (1) Diameter of largest bit 9"  
(2) Ground water encountered at none ft.  
(3) At what depth was first vein of water encountered 63 ft. Cased off: Yes No  
(4) Total depth of well 200 ft. Standing water level in well below ground surface when not pumping 3.2 ft.  
(5) Casing: Diameter of casing 6 3/4" Length of metal casing 43  
Are casing joints water tight? Yes No How were these joints sealed by welding \_\_\_\_\_  
by treaded sleeves \_\_\_\_\_  
Finished casing terminates 1 ft. above ground level 48 ft. below ground level.  
(6) Well cement grouted: Yes No To what depth 42 ft.  
(if answer to No. 6 is NO an acceptable explanation in detail is necessary \_\_\_\_\_)

(7) Yield of well: 19 gal. per min. No. of hours pump operated at this rate during test 1 hours \_\_\_\_\_ minutes.

(8) Log of materials encountered during drilling Clay sand, Stone, boulders  
and gravel, etc. See log.

I hereby certify that the above information concerning this well is true and correct.

Jerry Harley  
Well Driller  
Dept. of Geology, Mines and Water Resources  
License No. 145



NATIONAL TWO WEST  
 AND MEADOW CA  
 FREDERICK COUNTY HEALTH DEPARTMENT Quarters No. 5  
 Frederick County Approval Certificate For Well Installation  
 US DEPT OF INTERIOR Driller AUSTIN GARVER  
 D. 1100 OAK DRIVE S.W. Street or R.F.D.  
 WASHINGTON, PA 22042 Post Office  
 Location of property CATSKILL MOUNTAIN NATIONAL PARK Elk Fxville - DEERFIELD  
RD - RANGERS QUARTERS #5

If Subdivision: Name \_\_\_\_\_ Block or Section Lot No.


Well to furnish water to: House \_\_\_\_\_ Commercial establishment \_\_\_\_\_ Other \_\_\_\_\_

Lot Size: Width (front) \_\_\_\_\_ Depth (l. side) \_\_\_\_\_ Area of lot \_\_\_\_\_ sq.ft.  
 (rear) \_\_\_\_\_ (r. side) \_\_\_\_\_ acres

This application is made with the understanding that the well will be drilled only at the place designated by the Health Department and as shown in the sketch below. A completion certificate of this well must be filed by the driller, at the Health Department, within fifteen (15) days after completion of drilling. All well drilling operations will be carried out in accordance with regulations of the State Department of Health. Drilling at any other location, other than shown on sketch, VOIDS this approval certificate.

Date 11-4-83 Austin Garver  
 Signature of Applicant  
 Owner \_\_\_\_\_ Contractor \_\_\_\_\_ Well Driller ☒ Agent

TO BE COMPLETED BY HEALTH DEPARTMENT AND MADE A PART OF THIS APPLICATION 660  
660



**VOID**  
 AFTER THIS DATE  
5/31/84

**NOTICE - READ CAREFULLY**  
 The applicant for this permit is herewith advised that the property to be served by this system is in an area shown to be in the Frederick County Comprehensive Water and Sewerage Plan. The system for which this permit is issued is of a temporary nature and the applicant is herewith advised that it must be disconnected and connected to any such future community system if and when it becomes available to serve the property.

The property described above has been inspected and the well site approved as shown.  
 Date of approval 11-7-83 Sanitarian Edward F. Jorg



<b>C 1</b> <b>09830</b>		SEQUENCE NO. (MDE USE ONLY)		<b>STATE OF MARYLAND</b> <b>WELL COMPLETION REPORT</b> FILL IN THIS FORM COMPLETELY PLEASE TYPE		Jim Brown No. 3	
ST/CO USE ONLY DATE Received MM    DD    YY 8    13		DATE WELL COMPLETED MM    DD    YY 4/24/02		Depth of Well 22    800    26 (TO NEAREST FOOT)		PERMIT NO. FROM "PERMIT TO DRILL WELL" ER-94-3010	
OWNER <u>CATACTIN MOUNTAIN PARK</u> STREET OR RFD <u>MANAHAN</u> SUBDIVISION _____		TOWN <u>Foxville</u> SECTION _____ LOT _____					

<b>WELL LOG</b> Not required for driven wells			<b>GROUTING RECORD</b>			<b>C 3</b>																																																																																																																																																										
STATE THE KIND OF FORMATIONS PENETRATED, THEIR COLOR, DEPTH, THICKNESS AND IF WATER BEARING			WELL HAS BEEN GROUTED (Circle Appropriate Box)			<b>PUMPING TEST</b>																																																																																																																																																										
DESCRIPTION (Use additional sheets if needed)			TYPE OF GROUTING MATERIAL (Circle one) CEMENT <b>CM</b> BENTONITE CLAY <b>BC</b>			HOURS PUMPED (nearest hour) <u>3</u>																																																																																																																																																										
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FEET</th> <th>check if water bearing</th> </tr> <tr> <th>FROM</th> <th>TO</th> </tr> </thead> <tbody> <tr> <td>Top soil</td> <td>0 2</td> <td></td> </tr> <tr> <td>Shale</td> <td>2 10</td> <td></td> </tr> <tr> <td>Green Mountain Rock</td> <td>10 260</td> <td>✓</td> </tr> <tr> <td>Line stone</td> <td>260 315</td> <td></td> </tr> <tr> <td>Quartz</td> <td>315 320</td> <td>✓</td> </tr> <tr> <td>Green Mountain Rock</td> <td>320 500</td> <td></td> </tr> <tr> <td>Line stone</td> <td>500 580</td> <td></td> </tr> <tr> <td>Green Mountain Rock</td> <td>580 700</td> <td></td> </tr> <tr> <td>Blue Rock</td> <td>700 800</td> <td></td> </tr> </tbody> </table>			FEET	check if water bearing	FROM	TO	Top soil	0 2		Shale	2 10		Green Mountain Rock	10 260	✓	Line stone	260 315		Quartz	315 320	✓	Green Mountain Rock	320 500		Line stone	500 580		Green Mountain Rock	580 700		Blue Rock	700 800		NO. OF BAGS <u>26</u> NO. OF POUNDS <u>2650</u> GALLONS OF WATER <u>150</u> DEPTH OF GROUT SEAL (to nearest foot) from <u>0</u> ft. to <u>30</u> ft. (enter 0 if from surface)			PUMPING RATE (gal. per min.) <u>6</u>																																																																																																																											
FEET	check if water bearing																																																																																																																																																															
FROM	TO																																																																																																																																																															
Top soil	0 2																																																																																																																																																															
Shale	2 10																																																																																																																																																															
Green Mountain Rock	10 260	✓																																																																																																																																																														
Line stone	260 315																																																																																																																																																															
Quartz	315 320	✓																																																																																																																																																														
Green Mountain Rock	320 500																																																																																																																																																															
Line stone	500 580																																																																																																																																																															
Green Mountain Rock	580 700																																																																																																																																																															
Blue Rock	700 800																																																																																																																																																															
			CASING RECORD casing types insert appropriate code below <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>ST</td> <td>CO</td> </tr> <tr> <td>STEEL</td> <td>CONCRETE</td> </tr> <tr> <td>PL</td> <td>OT</td> </tr> <tr> <td>PLASTIC</td> <td>OTHER</td> </tr> </table>			ST	CO	STEEL	CONCRETE	PL	OT	PLASTIC	OTHER	METHOD USED TO MEASURE PUMPING RATE <u>Bucket</u>																																																																																																																																																		
ST	CO																																																																																																																																																															
STEEL	CONCRETE																																																																																																																																																															
PL	OT																																																																																																																																																															
PLASTIC	OTHER																																																																																																																																																															
			MAIN CASING TYPE <u>ST</u> Nominal diameter top (main) casing (nearest inch) <u>8</u> Total depth of main casing (nearest foot) <u>62</u>			WATER LEVEL (distance from land surface) BEFORE PUMPING <u>50</u> ft. WHEN PUMPING <u>800</u> ft.																																																																																																																																																										
			OTHER CASING (if used) diameter inch    depth (feet) from    to			TYPE OF PUMP USED (for test) <b>A</b> air <b>P</b> piston <b>T</b> turbine <b>C</b> centrifugal <b>R</b> rotary <b>O</b> other (describe below) <b>J</b> jet <b>S</b> submersible																																																																																																																																																										
			SCREEN RECORD screen type or open hole insert appropriate code below <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>ST</td> <td>BR</td> <td>HO</td> </tr> <tr> <td>STEEL</td> <td>BRASS</td> <td>OPEN HOLE</td> </tr> <tr> <td>PL</td> <td>BRONZE</td> <td>OT</td> </tr> <tr> <td>PLASTIC</td> <td>OTHER</td> <td></td> </tr> </table>			ST	BR	HO	STEEL	BRASS	OPEN HOLE	PL	BRONZE	OT	PLASTIC	OTHER		PUMP INSTALLED DRILLER INSTALLED PUMP YES <b>NO</b> (CIRCLE) (YES or NO)																																																																																																																																														
ST	BR	HO																																																																																																																																																														
STEEL	BRASS	OPEN HOLE																																																																																																																																																														
PL	BRONZE	OT																																																																																																																																																														
PLASTIC	OTHER																																																																																																																																																															
NUMBER OF UNSUCCESSFUL WELLS: <u>1</u>			DEPTH (nearest ft.) <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td>1</td> <td>2</td> <td>3</td> <td>4</td> <td>5</td> <td>6</td> <td>7</td> <td>8</td> <td>9</td> <td>10</td> <td>11</td> <td>12</td> <td>13</td> <td>14</td> <td>15</td> <td>16</td> <td>17</td> <td>18</td> <td>19</td> <td>20</td> <td>21</td> <td>22</td> <td>23</td> <td>24</td> <td>25</td> <td>26</td> <td>27</td> <td>28</td> <td>29</td> <td>30</td> <td>31</td> <td>32</td> <td>33</td> <td>34</td> <td>35</td> <td>36</td> <td>37</td> <td>38</td> <td>39</td> <td>40</td> <td>41</td> <td>42</td> <td>43</td> <td>44</td> <td>45</td> <td>46</td> <td>47</td> <td>48</td> <td>49</td> <td>50</td> <td>51</td> <td>52</td> <td>53</td> <td>54</td> <td>55</td> <td>56</td> <td>57</td> <td>58</td> <td>59</td> <td>60</td> <td>61</td> <td>62</td> <td>63</td> <td>64</td> <td>65</td> <td>66</td> <td>67</td> <td>68</td> <td>69</td> <td>70</td> <td>71</td> <td>72</td> <td>73</td> <td>74</td> <td>75</td> <td>76</td> </tr> <tr> <td>1</td> <td>2</td> <td>3</td> <td>4</td> <td>5</td> <td>6</td> <td>7</td> <td>8</td> <td>9</td> <td>10</td> <td>11</td> <td>12</td> <td>13</td> <td>14</td> <td>15</td> <td>16</td> <td>17</td> <td>18</td> <td>19</td> <td>20</td> <td>21</td> <td>22</td> <td>23</td> <td>24</td> <td>25</td> <td>26</td> <td>27</td> <td>28</td> <td>29</td> <td>30</td> <td>31</td> <td>32</td> <td>33</td> <td>34</td> <td>35</td> <td>36</td> <td>37</td> <td>38</td> <td>39</td> <td>40</td> <td>41</td> <td>42</td> <td>43</td> <td>44</td> <td>45</td> <td>46</td> <td>47</td> <td>48</td> <td>49</td> <td>50</td> <td>51</td> <td>52</td> <td>53</td> <td>54</td> <td>55</td> <td>56</td> <td>57</td> <td>58</td> <td>59</td> <td>60</td> <td>61</td> <td>62</td> <td>63</td> <td>64</td> <td>65</td> <td>66</td> <td>67</td> <td>68</td> <td>69</td> <td>70</td> <td>71</td> <td>72</td> <td>73</td> <td>74</td> <td>75</td> <td>76</td> </tr> </table>			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	CASING HEIGHT (circle appropriate box and enter casing height) <b>+</b> above <b>-</b> below    LAND SURFACE <u>2</u> (nearest foot)		
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76																																																																																					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76																																																																																					
WELL HYDROFRACTURED YES <b>NO</b> <b>Y</b> <b>N</b>			LOCATION OF WELL ON LOT SHOW PERMANENT STRUCTURES AND INDICATE NOT LESS THAN TWO DISTANCES (MEASUREMENTS TO WELL) <u>see plat</u>																																																																																																																																																													
CIRCLE APPROPRIATE LETTER <b>A</b> A WELL WAS ABANDONED AND SEALED WHEN THIS WELL WAS COMPLETED <b>E</b> ELECTRIC LOG OBTAINED <b>P</b> TEST WELL CONVERTED TO PRODUCTION WELL			DRILLERS LIC. NO. <u>MW D 0640</u> <u>George F. Easton</u> DRILLERS SIGNATURE (MUST MATCH SIGNATURE ON APPLICATION) LIC. NO. <u>MW D 481</u>			GRAVEL PACK IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68																																																																																																																																																										
I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.			MDE USE ONLY (NOT TO BE FILLED IN BY DRILLER) (E.R.O.S.) T _____ W Q _____			SITE SUPERVISOR (sign. of driller or journeyman)																																																																																																																																																										





09849 (MDE USE ONLY)		<b>STATE OF MARYLAND</b> <b>WELL COMPLETION REPORT</b> FILL IN THIS FORM COMPLETELY PLEASE TYPE		Jim Brown No. 4																																											
ST/CO USE ONLY DATE RECEIVED MM DD YY 8 13		DATE WELL COMPLETED 4/24/02 15 20		Depth of Well 22 500 26 (TO NEAREST FOOT)																																											
OWNER CATOOTW MINT PARK last name first name		STREET OR RFD MANAHAN RD		TOWN THIRYMANT																																											
SUBDIVISION NATIONAL PARK		SECTION 11		LOT 12																																											
<b>WELL LOG</b> Not required for driven wells STATE THE KIND OF FORMATIONS PENETRATED, THEIR COLOR, DEPTH, THICKNESS AND IF WATER BEARING		<b>GROUTING RECORD</b> WELL HAS BEEN GROUTED (Circle Appropriate Box) TYPE OF GROUTING MATERIAL (Circle one) CEMENT <input checked="" type="checkbox"/> BENTONITE CLAY <input checked="" type="checkbox"/> NO. OF BAGS 27 NO. OF POUNDS 2700 GALLONS OF WATER 162 DEPTH OF GROUT SEAL (to nearest foot) from 48 TOP 52 ft. to 54 BOTTOM 58 ft. (enter 0 if from surface)		<b>PUMPING TEST</b> HOURS PUMPED (nearest hour) 3 PUMPING RATE (gal. per min.) 100 METHOD USED TO MEASURE PUMPING RATE Bucket WATER LEVEL (distance from land surface) BEFORE PUMPING 50 ft. WHEN PUMPING 500 ft. TYPE OF PUMP USED (for test) <input checked="" type="checkbox"/> A air <input type="checkbox"/> P piston <input type="checkbox"/> T turbine <input type="checkbox"/> C centrifugal <input type="checkbox"/> R rotary <input type="checkbox"/> O other (describe below) <input type="checkbox"/> J jet <input type="checkbox"/> S submersible																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th rowspan="2">DESCRIPTION (Use additional sheets if needed)</th> <th colspan="2">FEET</th> <th rowspan="2">check if water bearing</th> </tr> <tr> <th>FROM</th> <th>TO</th> </tr> </thead> <tbody> <tr> <td>top soil</td> <td>0</td> <td>2</td> <td></td> </tr> <tr> <td>Shale</td> <td>2</td> <td>12</td> <td></td> </tr> <tr> <td>Green Mountain Rock</td> <td>12</td> <td>142</td> <td></td> </tr> <tr> <td>Quartz</td> <td>142</td> <td>148</td> <td>✓</td> </tr> <tr> <td>Brown shale</td> <td>148</td> <td>275</td> <td></td> </tr> <tr> <td>Blue stone</td> <td>148</td> <td>275</td> <td></td> </tr> <tr> <td>Green Mountain Rock</td> <td>275</td> <td>315</td> <td>✓</td> </tr> <tr> <td>Blue stone</td> <td>315</td> <td>380</td> <td></td> </tr> <tr> <td>Green Mountain Rock</td> <td>380</td> <td>500</td> <td>✓</td> </tr> </tbody> </table>		DESCRIPTION (Use additional sheets if needed)	FEET		check if water bearing	FROM	TO	top soil	0	2		Shale	2	12		Green Mountain Rock	12	142		Quartz	142	148	✓	Brown shale	148	275		Blue stone	148	275		Green Mountain Rock	275	315	✓	Blue stone	315	380		Green Mountain Rock	380	500	✓	<b>CASING RECORD</b> casing types insert appropriate code below <input checked="" type="checkbox"/> ST STEEL <input type="checkbox"/> CO CONCRETE <input type="checkbox"/> PL PLASTIC <input type="checkbox"/> OT OTHER MAIN CASING TYPE ST Nominal diameter top (main) casing (nearest inch) 8 Total depth of main casing (nearest foot) 57 60 61 63 64 66 70 OTHER CASING (if used) diameter depth (feet) inch from to EACH CASING		<b>PUMP INSTALLED</b> DRILLER INSTALLED PUMP (CIRCLE) (YES or NO) YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> IF DRILLER INSTALLS PUMP, THIS SECTION MUST BE COMPLETED FOR ALL WELLS. TYPE OF PUMP INSTALLED PLACE (A,C,J,P,R,S,T,O) IN BOX 29. CAPACITY: GALLONS PER MINUTE (to nearest gallon) 31 35 PUMP HORSE POWER 37 41 PUMP COLUMN LENGTH (nearest ft.) 43 47 CASING HEIGHT (circle appropriate box and enter casing height) <input checked="" type="checkbox"/> above LAND SURFACE <input type="checkbox"/> below 2 (nearest foot) LOCATION OF WELL ON LOT SHOW PERMANENT STRUCTURES AND INDICATE NOT LESS THAN TWO DISTANCES (MEASUREMENTS TO WELL) per plot	
DESCRIPTION (Use additional sheets if needed)	FEET		check if water bearing																																												
	FROM	TO																																													
top soil	0	2																																													
Shale	2	12																																													
Green Mountain Rock	12	142																																													
Quartz	142	148	✓																																												
Brown shale	148	275																																													
Blue stone	148	275																																													
Green Mountain Rock	275	315	✓																																												
Blue stone	315	380																																													
Green Mountain Rock	380	500	✓																																												
NUMBER OF UNSUCCESSFUL WELLS: 0 WELL HYDROFRACTURED <input checked="" type="checkbox"/> YES <input checked="" type="checkbox"/> NO CIRCLE APPROPRIATE LETTER A A WELL WAS ABANDONED AND SEALED WHEN THIS WELL WAS COMPLETED E ELECTRIC LOG OBTAINED P TEST WELL CONVERTED TO PRODUCTION WELL I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.		<b>SCREEN RECORD</b> screen type or open hole insert appropriate code below <input checked="" type="checkbox"/> ST STEEL <input type="checkbox"/> BR BRASS <input type="checkbox"/> HO OPEN HOLE <input type="checkbox"/> PL PLASTIC <input type="checkbox"/> OT OTHER C 2 DEPTH (nearest ft.) 1 40 55 500 8 9 11 15 17 21 23 24 26 30 32 36 38 39 41 45 47 51 SLOT SIZE 1 2 3 DIAMETER OF SCREEN (NEAREST INCH) 56 60 from to		GRAVEL PACK IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68 MDE USE ONLY (NOT TO BE FILLED IN BY DRILLER) T (E.R.O.S.) W Q 70 72 74 75 76 TELESCOPE CASING LOG INDICATOR OTHER DATA																																											
DRILLERS LIC. NO. 1 MW D 040 DRILLERS SIGNATURE (MUST MATCH SIGNATURE ON APPLICATION) LIC. NO. 1 MW D 481 SITE SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)		DATE 4/15/02																																													



<b>C1</b> 3784		SEQUENCE NO. (MDE USE ONLY)		<b>STATE OF MARYLAND</b> <b>WELL COMPLETION REPORT</b> FILL IN THIS FORM COMPLETELY PLEASE TYPE		Ike Smith Test Hole	
1 2 3 4 5 6 (THIS NUMBER IS TO BE PUNCHED IN COLS. 3-6 ON ALL CARDS)							
ST/CO USE ONLY DATE RECEIVED MM DO YY 8 13		DATE WELL COMPLETED MM DO YY 8/14/06		Depth of Well 22 800 26 (TO NEAREST FOOT)		PERMIT NO. FROM "PERMIT TO DRILL WELL" FR-95-0125	
OWNER CATACTIN MOUNTAIN PARK		STREET OR RFD MANAHAN ROAD		TOWN FOXVILLE			
SUBDIVISION IKE SMITH SITE		SECTION W-1		LOT CAMP 4			

<b>WELL LOG</b> Not required for driven wells			<b>GROUTING RECORD</b> WELL HAS BEEN GROUTED (Circle Appropriate Box) <b>Y</b> <b>N</b>			<b>C 3</b>		
STATE THE KIND OF FORMATIONS PENETRATED, THEIR COLOR, DEPTH, THICKNESS AND IF WATER BEARING			TYPE OF GROUTING MATERIAL (Circle one) CEMENT <b>CM</b> BENTONITE CLAY <b>BC</b>			PUMPING TEST		
DESCRIPTION (Use additional sheets if needed)	FEET		check if water bearing	NO. OF BAGS 52 NO. OF POUNDS 5200		HOURS PUMPED (nearest hour) 3		
	FROM	TO		GALLONS OF WATER 5200		PUMPING RATE (gal. per min.) 10		
top soil	0	1		DEPTH OF GROUT SEAL (to nearest foot)		METHOD USED TO MEASURE PUMPING RATE Bucket		
green mount rock	1	4		from 0 to 78 ft.		WATER LEVEL (distance from land surface)		
lose rock	4	7	✓	(enter 0 if from surface)		BEFORE PUMPING 50 ft.		
clay	7	10		Casing Record		WHEN PUMPING 800 ft.		
green mount rock	10	16		casing types insert appropriate code below		TYPE OF PUMP USED (for test)		
gravel	16	17	✓	STEEL <b>ST</b> CONCRETE <b>CO</b>		<b>A</b> air <b>P</b> piston <b>T</b> turbine		
lose rock & clay	17	25		PLASTIC <b>PL</b> OTHER <b>OT</b>		<b>C</b> centrifugal <b>R</b> rotary <b>O</b> other (describe below)		
gravel	25	28	✓	MAIN CASING TYPE		<b>J</b> jet <b>S</b> submersible		
green mount rock	28	52		Nominal diameter top (main) casing (nearest inch) 8		PUMP INSTALLED		
open	52	54		Total depth of main casing (nearest foot) 80		DRILLER INSTALLED PUMP YES <b>NO</b>		
green mount rock	54	82		OTHER CASING (if used) diameter inch depth (feet) from to		IF DRILLER INSTALLS PUMP, THIS SECTION MUST BE COMPLETED FOR ALL WELLS.		
fractured	82	83	✓			TYPE OF PUMP INSTALLED		
green mount rock	83	385				PLACE (A,C,J,P,R,S,T,O) IN BOX 29.		
green mount rock	385	600				CAPACITY: GALLONS PER MINUTE (to nearest gallon)		
quartz	600	675				PUMP HORSE POWER		
blue slate	675	800				PUMP COLUMN LENGTH (nearest ft.)		
green mount rock	675	800				CASING HEIGHT (circle appropriate box and enter casing height)		
						<b>E</b> above <b>below</b> 2 (nearest foot)		
						LOCATION OF WELL ON LOT		
						SHOW PERMANENT STRUCTURE SUCH AS BUILDING, SEPTIC TANKS, AND /OR LANDMARKS AND INDICATE NOT LESS THAN TWO DISTANCES (MEASUREMENTS TO WELL)		

NUMBER OF UNSUCCESSFUL WELLS: 0		WELL HYDROFRACTURED <b>Y</b> <b>N</b>		CIRCLE APPROPRIATE LETTER <b>A</b> A WELL WAS ABANDONED AND SEALED WHEN THIS WELL WAS COMPLETED <b>E</b> ELECTRIC LOG OBTAINED <b>P</b> TEST WELL CONVERTED TO PRODUCTION WELL	
I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.					
DRILLER'S LIC. NO. 1 MW D 040		DRILLER'S SIGNATURE (MUST MATCH SIGNATURE ON APPLICATION)		SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)	
DRILLER'S SIGNATURE (MUST MATCH SIGNATURE ON APPLICATION)		LIC. NO. 1 MW D 481			
GRAVEL PACK IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68		MDE USE ONLY (NOT TO BE FILLED IN BY DRILLER) (E.R.O.S.)		TELESCOPE CASING LOG INDICATOR OTHER DATA	



<b>C1</b> 3783 <small>(THIS NUMBER IS TO BE PUNCHED IN COLS. 3-6 ON ALL CARDS)</small>	SEQUENCE NO. <small>(MDE USE ONLY)</small>	<b>STATE OF MARYLAND</b> <b>WELL COMPLETION REPORT</b> FILL IN THIS FORM COMPLETELY PLEASE TYPE		Test Hole at Blue Blazes																																																		
ST/CO USE ONLY DATE Received: MM DO YY 8 13		DATE WELL COMPLETED 8/14/06		Depth of Well 600 <small>(TO NEAREST FOOT)</small>																																																		
OWNER: CATOCTIN MOUNTAIN PARK STREET OR RFD: PARK CENTRAL ROAD SUBDIVISION: MISTY MNT SITE		TOWN: Foxville SECTION: W #1 LOT: Camp 1		PERMIT NO. FROM "PERMIT TO DRILL WELL" FR-95-0126																																																		
<b>WELL LOG</b> <small>Not required for driven wells</small> STATE THE KIND OF FORMATIONS PENETRATED, THEIR COLOR, DEPTH, THICKNESS AND IF WATER BEARING <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th rowspan="2">DESCRIPTION (Use additional sheets if needed)</th> <th colspan="2">FEET</th> <th rowspan="2">check if water bearing</th> </tr> <tr> <th>FROM</th> <th>TO</th> </tr> </thead> <tbody> <tr> <td>top soil</td> <td>0</td> <td>2</td> <td></td> </tr> <tr> <td>green mount rock</td> <td>2</td> <td>12</td> <td></td> </tr> <tr> <td>clay</td> <td>12</td> <td>34</td> <td></td> </tr> <tr> <td>soft mud</td> <td>34</td> <td>35</td> <td>✓</td> </tr> <tr> <td>green mount rock</td> <td>35</td> <td>120</td> <td></td> </tr> <tr> <td>Fractured</td> <td>120</td> <td>121</td> <td>✓</td> </tr> <tr> <td>Green mount rock</td> <td>121</td> <td>410</td> <td>✓</td> </tr> <tr> <td>green mount rock</td> <td>410</td> <td>425</td> <td>✓</td> </tr> <tr> <td>Quartz</td> <td></td> <td></td> <td></td> </tr> <tr> <td>green mount rock</td> <td>425</td> <td>600</td> <td></td> </tr> </tbody> </table>		DESCRIPTION (Use additional sheets if needed)	FEET		check if water bearing	FROM	TO	top soil	0	2		green mount rock	2	12		clay	12	34		soft mud	34	35	✓	green mount rock	35	120		Fractured	120	121	✓	Green mount rock	121	410	✓	green mount rock	410	425	✓	Quartz				green mount rock	425	600		<b>GROUTING RECORD</b> WELL HAS BEEN GROUTED (Circle Appropriate Box) TYPE OF GROUTING MATERIAL (Circle one) CEMENT <b>(CM)</b> BENTONITE CLAY <b>(BC)</b> NO. OF BAGS 22 NO. OF POUNDS 2200 GALLONS OF WATER 132 DEPTH OF GROUT SEAL (to nearest foot) from 0 ft. to 13 ft. <small>(enter 0 if from surface)</small> <b>CASING RECORD</b> casing types insert appropriate code below <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td><b>ST</b> STEEL</td> <td><b>CO</b> CONCRETE</td> </tr> <tr> <td><b>PL</b> PLASTIC</td> <td><b>OT</b> OTHER</td> </tr> </table> MAIN CASING TYPE St 8 80 <small>60 61 63 64 66 70</small> OTHER CASING (if used) diameter inch depth (feet) from to EACH CASING			<b>ST</b> STEEL	<b>CO</b> CONCRETE	<b>PL</b> PLASTIC	<b>OT</b> OTHER
DESCRIPTION (Use additional sheets if needed)	FEET		check if water bearing																																																			
	FROM	TO																																																				
top soil	0	2																																																				
green mount rock	2	12																																																				
clay	12	34																																																				
soft mud	34	35	✓																																																			
green mount rock	35	120																																																				
Fractured	120	121	✓																																																			
Green mount rock	121	410	✓																																																			
green mount rock	410	425	✓																																																			
Quartz																																																						
green mount rock	425	600																																																				
<b>ST</b> STEEL	<b>CO</b> CONCRETE																																																					
<b>PL</b> PLASTIC	<b>OT</b> OTHER																																																					

NUMBER OF UNSUCCESSFUL WELLS: 0  
 WELL HYDROFRACTURED: **Y** **(N)**  
 CIRCLE APPROPRIATE LETTER  
**A** A WELL WAS ABANDONED AND SEALED WHEN THIS WELL WAS COMPLETED  
**E** ELECTRIC LOG OBTAINED  
**P** TEST WELL CONVERTED TO PRODUCTION WELL  
 I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.  
 DRILLERS LIC. NO. 1 MW D 040  
 George F. Eastman  
 DRILLERS SIGNATURE  
(MUST MATCH SIGNATURE ON APPLICATION)  
 LIC. NO. 1 MW D 0481  
 SITE SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)

**SCREEN RECORD**  
 screen type or open hole insert appropriate code below  

<b>ST</b> STEEL	<b>BR</b> BRASS	<b>HO</b> OPEN HOLE
<b>PL</b> PLASTIC	<b>OT</b> OTHER	

**DEPTH (nearest ft.)**  
 78 600  
 1 8 9 11 15 17 21  
 2 23 24 26 30 32 36  
 3 38 39 41 45 47 51  
 4 53 55 57 59 61 63 65 67 69 71 73 75 77 79 81 83 85 87 89 91 93 95 97 99 101 103 105 107 109 111 113 115 117 119 121 123 125 127 129 131 133 135 137 139 141 143 145 147 149 151 153 155 157 159 161 163 165 167 169 171 173 175 177 179 181 183 185 187 189 191 193 195 197 199 201 203 205 207 209 211 213 215 217 219 221 223 225 227 229 231 233 235 237 239 241 243 245 247 249 251 253 255 257 259 261 263 265 267 269 271 273 275 277 279 281 283 285 287 289 291 293 295 297 299 301 303 305 307 309 311 313 315 317 319 321 323 325 327 329 331 333 335 337 339 341 343 345 347 349 351 353 355 357 359 361 363 365 367 369 371 373 375 377 379 381 383 385 387 389 391 393 395 397 399 401 403 405 407 409 411 413 415 417 419 421 423 425 427 429 431 433 435 437 439 441 443 445 447 449 451 453 455 457 459 461 463 465 467 469 471 473 475 477 479 481 483 485 487 489 491 493 495 497 499 501 503 505 507 509 511 513 515 517 519 521 523 525 527 529 531 533 535 537 539 541 543 545 547 549 551 553 555 557 559 561 563 565 567 569 571 573 575 577 579 581 583 585 587 589 591 593 595 597 599 601 603 605 607 609 611 613 615 617 619 621 623 625 627 629 631 633 635 637 639 641 643 645 647 649 651 653 655 657 659 661 663 665 667 669 671 673 675 677 679 681 683 685 687 689 691 693 695 697 699 701 703 705 707 709 711 713 715 717 719 721 723 725 727 729 731 733 735 737 739 741 743 745 747 749 751 753 755 757 759 761 763 765 767 769 771 773 775 777 779 781 783 785 787 789 791 793 795 797 799 801 803 805 807 809 811 813 815 817 819 821 823 825 827 829 831 833 835 837 839 841 843 845 847 849 851 853 855 857 859 861 863 865 867 869 871 873 875 877 879 881 883 885 887 889 891 893 895 897 899 901 903 905 907 909 911 913 915 917 919 921 923 925 927 929 931 933 935 937 939 941 943 945 947 949 951 953 955 957 959 961 963 965 967 969 971 973 975 977 979 981 983 985 987 989 991 993 995 997 999 1001 1003 1005 1007 1009 1011 1013 1015 1017 1019 1021 1023 1025 1027 1029 1031 1033 1035 1037 1039 1041 1043 1045 1047 1049 1051 1053 1055 1057 1059 1061 1063 1065 1067 1069 1071 1073 1075 1077 1079 1081 1083 1085 1087 1089 1091 1093 1095 1097 1099 1101 1103 1105 1107 1109 1111 1113 1115 1117 1119 1121 1123 1125 1127 1129 1131 1133 1135 1137 1139 1141 1143 1145 1147 1149 1151 1153 1155 1157 1159 1161 1163 1165 1167 1169 1171 1173 1175 1177 1179 1181 1183 1185 1187 1189 1191 1193 1195 1197 1199 1201 1203 1205 1207 1209 1211 1213 1215 1217 1219 1221 1223 1225 1227 1229 1231 1233 1235 1237 1239 1241 1243 1245 1247 1249 1251 1253 1255 1257 1259 1261 1263 1265 1267 1269 1271 1273 1275 1277 1279 1281 1283 1285 1287 1289 1291 1293 1295 1297 1299 1301 1303 1305 1307 1309 1311 1313 1315 1317 1319 1321 1323 1325 1327 1329 1331 1333 1335 1337 1339 1341 1343 1345 1347 1349 1351 1353 1355 1357 1359 1361 1363 1365 1367 1369 1371 1373 1375 1377 1379 1381 1383 1385 1387 1389 1391 1393 1395 1397 1399 1401 1403 1405 1407 1409 1411 1413 1415 1417 1419 1421 1423 1425 1427 1429 1431 1433 1435 1437 1439 1441 1443 1445 1447 1449 1451 1453 1455 1457 1459 1461 1463 1465 1467 1469 1471 1473 1475 1477 1479 1481 1483 1485 1487 1489 1491 1493 1495 1497 1499 1501 1503 1505 1507 1509 1511 1513 1515 1517 1519 1521 1523 1525 1527 1529 1531 1533 1535 1537 1539 1541 1543 1545 1547 1549 1551 1553 1555 1557 1559 1561 1563 1565 1567 1569 1571 1573 1575 1577 1579 1581 1583 1585 1587 1589 1591 1593 1595 1597 1599 1601 1603 1605 1607 1609 1611 1613 1615 1617 1619 1621 1623 1625 1627 1629 1631 1633 1635 1637 1639 1641 1643 1645 1647 1649 1651 1653 1655 1657 1659 1661 1663 1665 1667 1669 1671 1673 1675 1677 1679 1681 1683 1685 1687 1689 1691 1693 1695 1697 1699 1701 1703 1705 1707 1709 1711 1713 1715 1717 1719 1721 1723 1725 1727 1729 1731 1733 1735 1737 1739 1741 1743 1745 1747 1749 1751 1753 1755 1757 1759 1761 1763 1765 1767 1769 1771 1773 1775 1777 1779 1781 1783 1785 1787 1789 1791 1793 1795 1797 1799 1801 1803 1805 1807 1809 1811 1813 1815 1817 1819 1821 1823 1825 1827 1829 1831 1833 1835 1837 1839 1841 1843 1845 1847 1849 1851 1853 1855 1857 1859 1861 1863 1865 1867 1869 1871 1873 1875 1877 1879 1881 1883 1885 1887 1889 1891 1893 1895 1897 1899 1901 1903 1905 1907 1909 1911 1913 1915 1917 1919 1921 1923 1925 1927 1929 1931 1933 1935 1937 1939 1941 1943 1945 1947 1949 1951 1953 1955 1957 1959 1961 1963 1965 1967 1969 1971 1973 1975 1977 1979 1981 1983 1985 1987 1989 1991 1993 1995 1997 1999 2001 2003 2005 2007 2009 2011 2013 2015 2017 2019 2021 2023 2025 2027 2029 2031 2033 2035 2037 2039 2041 2043 2045 2047 2049 2051 2053 2055 2057 2059 2061 2063 2065 2067 2069 2071 2073 2075 2077 2079 2081 2083 2085 2087 2089 2091 2093 2095 2097 2099 2101 2103 2105 2107 2109 2111 2113 2115 2117 2119 2121 2123 2125 2127 2129 2131 2133 2135 2137 2139 2141 2143 2145 2147 2149 2151 2153 2155 2157 2159 2161 2163 2165 2167 2169 2171 2173 2175 2177 2179 2181 2183 2185 2187 2189 2191 2193 2195 2197 2199 2201 2203 2205 2207 2209 2211 2213 2215 2217 2219 2221 2223 2225 2227 2229 2231 2233 2235 2237 2239 2241 2243 2245 2247 2249 2251 2253 2255 2257 2259 2261 2263 2265 2267 2269 2271 2273 2275 2277 2279 2281 2283 2285 2287 2289 2291 2293 2295 2297 2299 2301 2303 2305 2307 2309 2311 2313 2315 2317 2319 2321 2323 2325 2327 2329 2331 2333 2335 2337 2339 2341 2343 2345 2347 2349 2351 2353 2355 2357 2359 2361 2363 2365 2367 2369 2371 2373 2375 2377 2379 2381 2383 2385 2387 2389 2391 2393 2395 2397 2399 2401 2403 2405 2407 2409 2411 2413 2415 2417 2419 2421 2423 2425 2427 2429 2431 2433 2435 2437 2439 2441 2443 2445 2447 2449 2451 2453 2455 2457 2459 2461 2463 2465 2467 2469 2471 2473 2475 2477 2479 2481 2483 2485 2487 2489 2491 2493 2495 2497 2499 2501 2503 2505 2507 2509 2511 2513 2515 2517 2519 2521 2523 2525 2527 2529 2531 2533 2535 2537 2539 2541 2543 2545 2547 2549 2551 2553 2555 2557 2559 2561 2563 2565 2567 2569 2571 2573 2575 2577 2579 2581 2583 2585 2587 2589 2591 2593 2595 2597 2599 2601 2603 2605 2607 2609 2611 2613 2615 2617 2619 2621 2623 2625 2627 2629 2631 2633 2635 2637 2639 2641 2643 2645 2647 2649 2651 2653 2655 2657 2659 2661 2663 2665 2667 2669 2671 2673 2675 2677 2679 2681 2683 2685 2687 2689 2691 2693 2695 2697 2699 2701 2703 2705 2707 2709 2711 2713 2715 2717 2719 2721 2723 2725 2727 2729 2731 2733 2735 2737 2739 2741 2743 2745 2747 2749 2751 2753 2755 2757 2759 2761 2763 2765 2767 2769 2771 2773 2775 2777 2779 2781 2783 2785 2787 2789 2791 2793 2795 2797 2799 2801 2803 2805 2807 2809 2811 2813 2815 2817 2819 2821 2823 2825 2827 2829 2831 2833 2835 2837 2839 2841 2843 2845 2847 2849 2851 2853 2855 2857 2859 2861 2863 2865 2867 2869 2871 2873 2875 2877 2879 2881 2883 2885 2887 2889 2891 2893 2895 2897 2899 2901 2903 2905 2907 2909 2911 2913 2915 2917 2919 2921 2923 2925 2927 2929 2931 2933 2935 2937 2939 2941 2943 2945 2947 2949 2951 2953 2955 2957 2959 2961 2963 2965 2967 2969 2971 2973 2975 2977 2979 2981 2983 2985 2987 2989 2991 2993 2995 2997 2999 3001 3003 3005 3007 3009 3011 3013 3015 3017 3019 3021 3023 3025 3027 3029 3031 3033 3035 3037 3039 3041 3043 3045 3047 3049 3051 3053 3055 3057 3059 3061 3063 3065 3067 3069 3071 3073 3075 3077 3079 3081 3083 3085 3087 3089 3091 3093 3095 3097 3099 3101 3103 3105 3107 3109 3111 3113 3115 3117 3119 3121 3123 3125 3127 3129 3131 3133 3135 3137 3139 3141 3143 3145 3147 3149 3151 3153 3155 3157 3159 3161 3163 3165 3167 3169 3171 3173 3175 3177 3179 3181 3183 3185 3187 3189 3191 3193 3195 3197 3199 3201 3203 3205 3207 3209 3211 3213 3215 3217 3219 3221 3223 3225 3227 3229 3231 3233 3235 3237 3239 3241 3243 3245 3247 3249 3251 3253 3255 3257 3259 3261 3263 3265 3267 3269 3271 3273 3275 3277 3279 3281 3283 3285 3287 3289 3291 3293 3295 3297 3299 3301 3303 3305 3307 3309 3311 3313 3315 3317 3319 3321 3323 3325 3327 3329 3331 3333 3335 3337 3339 3341 3343 3345 3347 3349 3351 3353 3355 3357 3359 3361 3363 3365 3367 3369 3371 3373 3375 3377 3379 3381 3383 3385 3387 3389 3391 3393 3395 3397 3399 3401 3403 3405 3407 3409 3411 3413 3415 3417 3419 3421 3423 3425 3427 3429 3431 3433 3435 3437 3439 3441 3443 3445 3447 3449 3451 3453 3455 3457 3459 3461 3463 3465 3467 3469 3471 3473 3475 3477 3479 3481 3483 3485 3487 3489 3491 3493 3495 3497 3499 3501 3503 3505 3507 3509 3511 3513 3515 3517 3519 3521 3523 3525 3527 3529 3531 3533 3535 3537 3539 3541 3543 3545 3547 3549 3551 3553 3555 3557 3559 3561 3563 3565 3567 3569 3571 3573 3575 3577 3579 3581 3583 3585 3587 3589 3591 3593 3595 3597 3599 3601 3603 3605 3607 3609 3611 3613 3615 3617 3619 3621 3623 3625 3627 3629 3631 3633 3635 3637 3639 3641 3643 3645 3647 3649 3651 3653 3655 3657 3659 3661 3663 3665 3667 3669 3671 3673 3675 3677 3679 3681 3683 3685 3687 3689 3691 3693 3695 3697 3699 3701 3703 3705 3707 3709 3711 3713 3715 3717 3719 3721 3723 3725 3727 3729 3731 3733 3735 3737 3739 3741 3743 3745 3747 3749 3751 3753 3755 3757 3759 3761 3763 3765 3767 3769 3771 3773 3775 3777 3779 3781 3783 3785 3787 3789 3791 3793 3795 3797 3799 3801 3803 3805 3807 3809 3811 3813 3815 3817 3819 3821 3823 3825 3827 3829 3831 3833 3835 3837 3839 3841 3843 3845 3847 3849 3851 3853 3855 3857 3859 3861 3863 3865 3867 3869 3871 3873 3875 3877 3879 3881 3883 3885 3887 3889 3891 3893 3895 3897 3899 3901 3903 3905 3907 3909 3911 3913 3915 3917 3919 3921 3923 3925 3927 3929 3931 3933 3935 3937 3939 3941 3943 3945 3947 3949 3951 3953 3955 3957 3959 3961 3963 3965 3967 3969 3971 3973 3975 3977 3979 3981 3983 3985 3987 3989 3991 3993 3995 3997 3999 4001 4003 4005 4007 4009 4011 4013 4015 4017 4019 4021 4023 4025 4027 4029 4031 4033 4035 4037 4039 4041 4043 4045 4047 4049 4051 4053 4055 4057 4059 4061 4063 4065 4067 4069 4071 4073 4075 4077 4079 4081 4083 4085 4087 4089 4091 4093 4095 4097 4099 4101 4103 4105 4107 4109 4111 4113 4115 4117 4119 4121 4123 4125 4127 4129 4131 4133 4135 4137 4139 4141 4143 4145 4147 4149 4151 4153 4155 4157 4159 4161 4163 4165 4167 4169 4171 4173 4175 4177 4179 4181 4183 4185 4187 4189 4191 4193 4195 4197 4199 4201 4203 4205 4207 4209 4211 4213 4215 4217 4219 4221 4223 4225 4227 4229 4231 4233 4235 4237 4239 4241 4243 4245 4247 4249 4251 4253 4255 4257 4259 4261 4263 4265 4267 4269 4271 4273 4275 4277 4279 4281 4283 4285 4287 4289 4291 4293 4295 4297 4299 4301 4303 4305 4307 4309 4311 4313 4315 4317 4319 4321 4323 4325 4327 4329 4331 4333 4335 4337 4339 4341 4343 4345 4347 4349 4351 4353 4355 4357 4359 4361 4363 4365 4367 4369 4371 4373 4375 4377 4379 4381 4383 4385 4387 4389 4391 4393 4395 4397 4399 4401 4403 4405 4407 4409 4411 4413 4415 4417 4419 4421 4423 4425 4427





ORIGINAL



Blue Blazes No. 2

L. FRANKLIN EASTERDAY, INC  
FIELD DATA SHEET

Date: 10/1/66

Page 1 of 1

Type of Test 24 HOUR PUMPING TEST

State Tag FR-95-0303 Owner: CATACTW MOUNTAIN PARK

Location: Misty Mountain #2 Water Level Below (M.P.): 41.6

Start Time: 9:20 M.P. Above Ground: 2'

ft. well, gpm 23

Min	Time	Level	GPM	Min	Time	Level	GPM	Min	Time	Level	GPM
1	9:21	48	23	35	9:55	93.1	23	13hrs	10:20	148.2	23
2	9:22	52.8	23	40	10:00	95.9	23	14hrs	11:20	149.0	23
3	9:23	56.4	23	45	10:05	97.9	23	15hrs	12:20	149.6	23
4	9:24	59.3	23	50	10:10	100.1	23	16hrs	1:20	150.2	23
5	9:25	62.2	23	55	10:15	101.9	23	18hrs	3:20	151.7	23
6	9:26	65.6	23	60	10:20	103.6	23	20hrs	5:20	153.0	23
7	9:27	66.8	23	90	10:50	112.2	23	22hrs	7:20	154.2	23
8	9:28	68.6	23	120	11:20	119.6	23	24hrs	9:20	154.5	23
9	9:29	70.6	23	150	11:50	123.5	23		10:40	155.2	23
10	9:30	72.2	23	180	12:20	127.2	23				
12	9:32	75.0	23	210	12:50	130.6	23				
14	9:34	77.2	23	240	1:20	133.8	23				
16	9:36	79.5	23	300	2:20	137.6	23				
18	9:38	81.5	23	360	3:20	140.15	23				
20	9:40	83.2	23	420	4:20	141.95	23				
22	9:42	85.0	23	480	5:20	143.40	23				
24	9:44	86.6	23	9hrs	6:20	144.6	23				
26	9:46	88.1	23	10hrs	7:20	145.7	23				
28	9:48	89.3	23	11hrs	8:20	146.7	23				
30	9:50	90.6	23	12hrs	9:20	147.3	23				

L. FRANKLIN EASTERDAY, INC  
FIELD DATA SHEET

Date: 10/12/06

Page 1 of 1

Type of Test      Recovery Check

State Tag FR-95-0303 Owner:

Location: Misty Mount #2

Water Level Below (M.P):

Start Time:

M.P Above Ground: 2'

ft. well,                      gpm

[illegible]

<b>C1</b> 5008		SEQUENCE NO. (MDE USE ONLY)		<b>STATE OF MARYLAND</b> <b>WELL COMPLETION REPORT</b> FILL IN THIS FORM COMPLETELY PLEASE TYPE		Test Hole at Bldg. 167	
1 2 3 6 (THIS NUMBER IS TO BE PUNCHED IN COLS. 3-6 ON ALL CARDS)		DATE WELL COMPLETED MM DD YY 9/28/04		Depth of Well 22 500 28 (TO NEAREST FOOT)		PERMIT NO. FROM "PERMIT TO DRILL WELL" ER-95-0304	
ST/CO USE ONLY DATE RECEIVED MM DD YY 8 13		DATE WELL COMPLETED 15 19 20					
OWNER CROFTON MOUNTAIN PARK		TOWN THURMONT		SECTION CAMP 1		LOT WELL 3	
STREET OR RFD MISTY MOUNT							
SUBDIVISION							

<b>WELL LOG</b> Not required for driven wells			<b>GROUTING RECORD</b> WELL HAS BEEN GROUTED (Circle Appropriate Box) <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO			<b>C 3</b> 1 2		
STATE THE KIND OF FORMATIONS PENETRATED, THEIR COLOR, DEPTH, THICKNESS AND IF WATER BEARING			TYPE OF GROUTING MATERIAL (Circle one) CEMENT <input checked="" type="checkbox"/> BENTONITE CLAY <input type="checkbox"/>			<b>PUMPING TEST</b>		
DESCRIPTION (Use additional sheets if needed)	FEET FROM	TO	check if water bearing	NO. OF BAGS 48	NO. OF POUNDS 4800	HOURS PUMPED (nearest hour) 3		
top soil	0	3		GALLONS OF WATER 288		PUMPING RATE (gal. per min.) 15		
shale	3	5		DEPTH OF GROUT SEAL (to nearest foot) from 0 ft. to 44 ft. (enter 0 if from surface)		METHOD USED TO MEASURE PUMPING RATE Bucket		
green mount rock	5	139		<b>CASING RECORD</b>			WATER LEVEL (distance from land surface)	
Fractured	139	140	✓	casing types insert appropriate code below			BEFORE PUMPING 50 ft.	
green mount rock	140	500		STEEL <input type="checkbox"/> CONCRETE <input type="checkbox"/> PLASTIC <input type="checkbox"/> OTHER <input type="checkbox"/>			WHEN PUMPING 500 ft.	
				MAIN CASING TYPE St 8 60			TYPE OF PUMP USED (for test)	
				Nominal diameter top (main) casing (nearest inch) 8			A air <input type="checkbox"/> P piston <input type="checkbox"/> T turbine <input type="checkbox"/>	
				Total depth of main casing (nearest foot) 60			C centrifugal <input type="checkbox"/> R rotary <input type="checkbox"/> O other (describe below)	
				OTHER CASING (if used) diameter inch			J jet <input type="checkbox"/> S submersible <input checked="" type="checkbox"/>	
				depth (feet) from to			PUMP INSTALLED	
				screen type or open hole			DRILLER INSTALLED PUMP (CIRCLE) (YES or NO)	
				STEEL <input type="checkbox"/> BRASS <input type="checkbox"/> OPEN HOLE <input type="checkbox"/>			IF DRILLER INSTALLS PUMP, THIS SECTION MUST BE COMPLETED FOR ALL WELLS.	
				BRONZE <input type="checkbox"/> PLASTIC <input type="checkbox"/> OTHER <input type="checkbox"/>			TYPE OF PUMP INSTALLED PLACE (A,C,J,P,R,S,T,O) IN BOX 29.	
				CAPACITY: GALLONS PER MINUTE (to nearest gallon)			PUMP HORSE POWER	
				PUMP COLUMN LENGTH (nearest ft.)			CASING HEIGHT (circle appropriate box and enter casing height)	
				C 2 DEPTH (nearest ft.)			LAND SURFACE	
				H 0 58 500			2 (nearest foot)	
				A 23 24 26 30 32 36			LOCATION OF WELL ON LOT	
				C 3 38 39 41 45 47 51			SHOW PERMANENT STRUCTURE SUCH AS BUILDING, SEPTIC TANKS, AND /OR LANDMARKS AND INDICATE NOT LESS THAN TWO DISTANCES (MEASUREMENTS TO WELL)	
				E 1 2 3			House 167	
				N DIAMETER OF SCREEN (NEAREST INCH)			100'	
				56 80			Rd	
				from to			+	
				GRAVEL PACK IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68			MDE USE ONLY (NOT TO BE FILLED IN BY DRILLER) -T (E.R.O.S.) W Q	
				70 72 74 75 76			TELESCOPE LOG INDICATOR OTHER DATA	

I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.		DRILLERS LIC. NO. 1 MW0040 DRILLER SIGNATURE (MUST MATCH SIGNATURE ON APPLICATION) LIC. NO. 1 MW0481	
SITE SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)			



STATE OF MARYLAND WELL COMPLETION REPORT FILL IN THIS FORM COMPLETELY PLEASE TYPE		1 Ke Smith Well	
(THIS NUMBER IS TO BE PUNCHED IN COLS. 3-6 ON ALL CARDS) ST/CO USE ONLY DATE RECEIVED MM DO YY 8 13		DATE WELL COMPLETED MM DO YY 9/21/04	
OWNER <u>CATCTIN MOUNTAIN PARK</u> STREET OR RFD <u>MANAHAN RD</u> SUBDIVISION <u>IKE SMITH SITE</u>		Depth of Well 22 <u>420</u> 26 (TO NEAREST FOOT)	
PERMIT NO. FROM "PERMIT TO DRILL WELL" <u>FR-95-0305</u>		28 29 30 31 32 33 34 35 36 37	
TOWN <u>Thurmont</u> SECTION <u>Well #2</u>		LOT <u>Well #2</u>	
WELL LOG			
Not required for driven wells			
STATE THE KIND OF FORMATIONS PENETRATED, THEIR COLOR, DEPTH, THICKNESS AND IF WATER BEARING			
DESCRIPTION (Use additional sheets if needed)	FEET FROM TO	check if water bearing	
top soil	0 3		
shale	3 15		
soft mud	15 18		
gravel	18 25		
green mount rock	25 35		
soft mud	35 37		
green mount rock	37 44		
gravel	44 51		
green mount rock	51 55		
quartz	55 98	✓	
green mount rock	98 379	✓	
open	379 380	✓	
green mount rock	380 420		
GRROUTING RECORD WELL HAS BEEN GROUTED (Circle Appropriate Box) TYPE OF GROUTING MATERIAL (Circle one) CEMENT <input checked="" type="checkbox"/> CM BENTONITE CLAY <input checked="" type="checkbox"/> BC NO. OF BAGS <u>41</u> NO. OF POUNDS <u>46100</u> GALLONS OF WATER <u>246</u> DEPTH OF GROUT SEAL (to nearest foot) from <u>0</u> ft. to <u>34</u> ft. (enter 0 if from surface)			
CASING RECORD casing types insert appropriate code below ST STEEL CO CONCRETE PL PLASTIC OT OTHER MAIN CASING TYPE <u>St</u> Nominal diameter top (main) casing (nearest inch) <u>8</u> Total depth of main casing (nearest foot) <u>55</u> 60 61 63 64 66 70			
OTHER CASING (if used) diameter inch depth (feet) from to E A C H I N G			
SCREEN RECORD screen type or open hole insert appropriate code below ST STEEL BR BRASS HO OPEN HOLE PL PLASTIC OT OTHER C 2 DEPTH (nearest ft.) 1 <u>40</u> 54 420 E A C H I N G			
NUMBER OF UNSUCCESSFUL WELLS: <u>0</u> WELL HYDROFRACTURED <input checked="" type="checkbox"/> Y <input checked="" type="checkbox"/> N			
CIRCLE APPROPRIATE LETTER A A WELL WAS ABANDONED AND SEALED WHEN THIS WELL WAS COMPLETED E ELECTRIC LOG OBTAINED P TEST WELL CONVERTED TO PRODUCTION WELL			
I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.			
DRILLER'S LIC. NO. <u>MWD 040</u> DRILLER'S SIGNATURE <u>George F. Eutenley</u> (MUST MATCH SIGNATURE ON APPLICATION) LIC. NO. <u>MWD 481</u> SITE SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)			
GRAVEL PACK IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68 MDE USE ONLY (NOT TO BE FILLED IN BY DRILLER) T (E.R.O.S.) W Q 70 72 74 75 76 TELESCOPE LOG OTHER DATA CASING INDICATOR			
PUMPING TEST C 3 HOURS PUMPED (nearest hour) <u>25</u> PUMPING RATE (gal. per min.) <u>100</u> METHOD USED TO MEASURE PUMPING RATE <u>DREICE</u> WATER LEVEL (distance from land surface) BEFORE PUMPING <u>17</u> ft. WHEN PUMPING <u>75</u> ft. TYPE OF PUMP USED (for test) A air P piston T turbine C centrifugal R rotary O other (describe below) J jet S submersible			
PUMP INSTALLED DRILLER INSTALLED PUMP (CIRCLE) (YES or NO) YES <input checked="" type="checkbox"/> NO <input type="checkbox"/> IF DRILLER INSTALLS PUMP, THIS SECTION MUST BE COMPLETED FOR ALL WELLS. TYPE OF PUMP INSTALLED PLACE (A,C,J,P,R,S,T,O) IN BOX 29. CAPACITY: GALLONS PER MINUTE (to nearest gallon) 31 35 PUMP HORSE POWER 37 41 PUMP COLUMN LENGTH (nearest ft.) 43 47 CASING HEIGHT (circle appropriate box and enter casing height) 49 above } LAND SURFACE 49 below } <u>2</u> (nearest foot)			
LOCATION OF WELL ON LOT SHOW PERMANENT STRUCTURE SUCH AS BUILDING, SEPTIC TANKS, AND /OR LANDMARKS AND INDICATE NOT LESS THAN TWO DISTANCES (MEASUREMENTS TO WELL) <u>old saw mill parking</u> 150'			





1ke Smith Well

L. FRANKLIN EASTERDAY, INC  
FIELD DATA SHEET

pump set  
300 FT

Date: 10/4/06

Page 1 of 1

Type of Test 24 HOUR PUMPING TEST

State Tag FR-95-0305 Owner: CATOCTIN MOUNTAIN PARK

Location: 1ke Smith #2 Water Level Below (M.P.): 16.45

Start Time: 9:00 M.P. Above Ground: 2 1/2

ft. well, 420 gpm 100

Min	Time	Level	GPM	Min	Time	Level	GPM	Min	Time	Level	GPM
1	9:01	22.7	100	35	9:35	50.3	100	13hrs	10:00	73.1	100
2	9:02	25.2	100	40	9:40	51.6	100	14hrs	11:00	73.4	100
3	9:03	27.5	100	45	9:45	52.7	100	15hrs	12:00	73.7	100
4	9:04	29.65	100	50	9:50	53.9	100	16hrs	1:00	74.0	100
5	9:05	31.4	100	55	9:55	54.6	100	18hrs	3:00	74.3	100
6	9:06	32.85	100	60	10:00	55.3	100	20hrs	5:00	74.7	100
7	9:07	34.3	100	90	10:30	58.6	100	22hrs	7:00	75.25	100
8	9:08	35.4	100	120	11:00	61.3	100	24hrs	9:00	75.3	100
9	9:09	36.45	100	150	11:30	62.8	100	25 1/2	10:30	75.45	100
10	9:10	37.7	100	180	12:00	64.5	100				
12	9:12	39.4	100	210	12:30	65.6	100				
14	9:14	40.8	100	240	1:00	66.4	100				
16	9:16		100	300	2:00	67.8	100				
18	9:18	43.5	100	360	3:00	69.1	100				
20	9:20	44.6	100	420	4:00	69.6	100				
22	9:22	45.4	100	480	5:00	70.3	100				
24	9:24	46.5	100	9hrs	6:00	70.9	100				
26	9:26	47.3	100	10hrs	7:00	71.2	100				
28	9:28	48.1	100	11hrs	8:00	71.8	100				
30	9:30	48.8	100	12hrs	9:00	72.5	100				

Page 1 of 1

State Tag

FR-95-0305

Owner: CATACTIN MOUNTAIN PARK

Location:

THE Smith #2

Water Level Below (M.P):

Start Time:

M.P Above Ground:

gpm

66

The Department of the Interior protects and manages the nation's natural resources and cultural heritage; provides scientific and other information about those resources; and honors its special responsibilities to American Indians, Alaska Natives, and affiliated Island Communities.

NPS D-32, June 2007

**National Park Service  
U.S. Department of the Interior**

**Natural Resource Program Center**



---

**Natural Resources Program Center**  
1201 Oak Ridge Drive, Suite 250  
Fort Collins, Colorado 80525

[www.nps.gov](http://www.nps.gov)

**EXPERIENCE YOUR AMERICA <sup>T</sup>**